BEAM 5S

Location	Station	Offset	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted For Dead Load Deflection
BK. S. ABUT.	103+91.77	-12.78	632.73	632.73
℄ BRG. S. ABUT.	103+93.57	-12.81	632.73	632.73
A	104+03.66	-12.95	632.76	632.75
B	104+13.74	-13.08	632.78	632.77
C	104+23.82	-13.19	632.81	632.80
℄ BRG. PIER 1	104+31.34	-13.26	632.82	632.82
D	104+41.42	-13.33	632.84	632.86
E	104+51.51	-13.39	632.85	632.91
F	104+61.59	-13.44	632.86	632.95
G	104+71.67	-13.46	632.87	632.99
H	104+81.76	-13.47	632.87	633.00
I	104+91.84	-13.46	632.88	632.99
J	105+01.92	-13.43	632.88	632.97
K	105+12.01	-13.39	632.88	632.93
L	105+22.09	-13.32	632.87	632.89
℄ BRG. PIER 2	105+30.66	-13.26	632.87	632.87
M	105+40.74	-13.16	632.86	632.86
N	105+50.83	-13.05	632.84	632.83
O	105+60.91	-12.92	632.83	632.82
℄ BRG. N. ABUT.	105+68.43	-12.81	632.81	632.81
BK. N. ABUT.	105+70.23	-12.78	632.81	632.81

BEAM 6S

Location	Station	Offset	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted For Dead Load Deflection
BK. S. ABUT.	103+91.65	-20.20	632.58	632.58
℄ BRG. S. ABUT.	103+93.46	-20.22	632.58	632.58
A	104+03.55	-20.37	632.61	632.60
B	104+13.65	-20.49	632.64	632.62
C	104+23.75	-20.60	632.66	632.65
℄ BRG. PIER 1	104+31.27	-20.67	632.67	632.67
D	104+41.37	-20.75	632.69	632.72
E	104+51.47	-20.81	632.70	632.77
F	104+61.56	-20.85	632.71	632.81
G	104+71.66	-20.88	632.72	632.84
H	104+81.76	-20.89	632.73	632.86
I	104+91.85	-20.88	632.73	632.85
J	105+01.95	-20.85	632.73	632.82
K	105+12.05	-20.80	632.73	632.79
L	105+22.14	-20.74	632.72	632.75
℄ BRG. PIER 2	105+30.73	-20.67	632.72	632.72
M	105+40.82	-20.58	632.71	632.71
N	105+50.92	-20.46	632.69	632.68
O	105+61.01	-20.33	632.68	632.67
℄ BRG. N. ABUT.	105+68.54	-20.22	632.67	632.67
BK. N. ABUT.	105+70.35	-20.20	632.66	632.66

benesch
engineers · scientists · planners
Alfred Benesch & Company
205 North Michigan Avenue, Suite 2400
Chicago, Illinois 60601
312-565-0450 Job No. 10093

FILE NAME = 01161000.60J16_008_slabelevs_3.dgn	USER NAME = jsurber	DESIGNED - JOB	REVISED -
		CHECKED - DJM	REVISED -
	PLOT SCALE =	DRAWN - FSM	REVISED -
	PLOT DATE = 12/20/2012	CHECKED - RMM	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

TOP OF SLAB ELEVATIONS (3 OF 3)
STRUCTURE NO. 016-1000/1001
SHEET NO. 58 OF SA40 SHEETS

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
372	2013-038B-R	COOK	821	256
		CONTRACT NO. 60J16		
		ILLINOIS FED. AID PROJECT		

X:\10000S\10093\Eng_Docs_Phase_II\SN_016_1000_1001_1st_Ave_over_47th_St\Final\01161000_60J16_008_slabelevs_3.dgn
9:18:58 AM
7/14/2014