



- ROADWORK LEGEND**
- ① PROPOSED HOT-MIX ASPHALT SURFACE REMOVAL - 2 1/4"
 - ① PROPOSED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70 - 1 1/2"
 - ① PROPOSED POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50 - 3/4"

 - ② PROPOSED SIDEWALK REMOVAL
 - ② PROPOSED PCC SIDEWALK, 5"
 - ② PROPOSED DETECTABLE WARNINGS
 - ② PROPOSED REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL
- SEE GENERAL NOTES

- PAVEMENT MARKINGS**
- (A) THERMOPLASTIC PAVEMENT MARKING - LINE 4" (WHITE) (10' DASH, 30' SKIP)
 - (B) THERMOPLASTIC PAVEMENT MARKING - LINE 4" (YELLOW) (10' DASH, 30' SKIP)
 - (C) THERMOPLASTIC PAVEMENT MARKING - LINE 4" (YELLOW)
 - (D) THERMOPLASTIC PAVEMENT MARKING - LINE 6" (WHITE)
 - (E) THERMOPLASTIC PAVEMENT MARKING - LINE 8" (WHITE)
 - (F) THERMOPLASTIC PAVEMENT MARKING - LINE 8" (YELLOW)
 - (G) THERMOPLASTIC PAVEMENT MARKING - LINE 12" (WHITE)
 - (H) THERMOPLASTIC PAVEMENT MARKING - LINE 12" (YELLOW)
 - (J) THERMOPLASTIC PAVEMENT MARKING - LINE 24" (WHITE)
 - (K) THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS

FILE NAME =	USER NAME = Tariqfm	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	ROADWAY AND PAVEMENT MARKING PLAN KIRCHOFF RD. (NEW WILKE RD. TO CENTRAL AVE.)	F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
es:\pwork\pwork\dot\tariqfm\d0241225\0109011-sht-plan.dgn	DRAWN -	REVISED -	3518			0405.2-RS	COOK	24	9	
PLOT SCALE = 100.0000' / in.	CHECKED -	REVISED -	CONTRACT NO. 60M23							
PLOT DATE = 7/11/2014	DATE -	REVISED -	ILLINOIS FED. AID PROJECT							