

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	ROADWAY 0005				
21101615	TOPSOIL FURNISH AND PLACE, 4"	SO YD	185	185				
25200110	SODDING, SALT TOLERANT	SO YD	185	185				
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	33	33				
40600827	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	899	899				
40600895	CONSTRUCTING TEST STRIP	EACH	1	1				
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	331	331				
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX 5D, N70	TON	1829	1829				
42001300	PROTECTIVE COAT	SO YD	573	573				
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SO YD	40	40				
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SO FT	1650	1650				
42400800	DETECTABLE WARNINGS	SO FT	170	170				
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SO YD	21782	21782				

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	ROADWAY 0005				
44000200	DRIVEWAY PAVEMENT REMOVAL	SO YD	40	40				
44000600	SIDEWALK REMOVAL	SO FT	1650	1650				
44201777	CLASS D PATCHES, TYPE II, 11 INCH	SO YD	105	105				
44201781	CLASS D PATCHES, TYPE III, 11 INCH	SO YD	39	39				
44201783	CLASS D PATCHES, TYPE IV, 11 INCH	SO YD	485	485				
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	15	15				
* 66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	15	15				
* 66900450	SPECIAL WASTE PLANS AND REPORTS	L SUM	1	1				
* 66900530	SOIL DISPOSAL ANALYSIS	EACH	1	1				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3				
67100100	MOBILIZATION	L SUM	1	1				
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1				
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1				
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1				

* Specialty Items

Rev.

FILE NAME :	USER NAME : oobawa	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	MICHIGAN AVE. FROM GARFIELD BLVD. TO 60TH ST. SUMMARY OF QUANTITIES	F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
6:\p\work\oobawa\oobawa\027748-00382-11-plan.dgn		DRAWN -	REVISED -			2911	2011-085-R5	COOK	17	3	
PLOT SCALE = 1/8" = 100'		CHECKED -	REVISED -			CONTRACT NO. 60R12					
PLOT DATE = 7/10/2014		DATE -	REVISED -			FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT					