

ACNHPP

ACHSIP

8D/20 FED/ST

90/10 FED/ST

CONSTRUCTION CODE

URBAN

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE					
				0005	0005	0021	0021		
				RESURFACING	RESURFACING	SAFETY	SAFETY		
		COOK COUNTY	KANE COUNTY	COOK COUNTY	KANE COUNTY				
28000400	PERIMETER EROSION BARRIER	FOOT	29,375			27,971	1,404		
28000510	INLET FILTERS	EACH	12			11	1		
28100101	STONE RIPRAP, CLASS A1	SQ YD	380			350	30		
28200200	FILTER FABRIC	SQ YD	380			350	30		
35100300	AGGREGATE BASE COURSE, TYPE A 4"	SQ YD	14,413			13,747	666		
40600827	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	2,480	2,336	144				
40600895	CONSTRUCTING TEST STRIP	EACH	2	2					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	673	504	169				
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	5,284	4,983	301				
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	55,979	52,315	3,664				
44000500	COMBINATION CURB AND CUTTER REMOVAL	FOOT	50	50					
44004250	PAVED SHOULDER REMOVAL	SQ YD	5,313	4,996	317				
44201803	CLASS D PATCHES, TYPE II, 13 INCH	SQ YD	1,213	1,192	21				
44201807	CLASS D PATCHES, TYPE III, 13 INCH	SQ YD	544	490	54				

FILE NAME: \*FILEL\*

SHT\_PLAN

USER NAME - *USER*	DESIGNED - MTM	REVISED -
	DRAWN - MTM	REVISED -
PLOT SCALE - *SCALE*	CHECKED - BA	REVISED -
PLOT DATE - *DATE*	DATE -	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

IL RTE 68 (DUNDEE ROAD) - PRAIRIE LAKE ROAD TO IL 62  
SUMMARY OF QUANTITIES

SCALE: N.T.S. SHEET 2 OF 6 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
343	631 RS-3	KANE/COOK	73	4
CONTRACT NO. 60T04			ILLINOIS FED. AID PROJECT	