

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	0005	0021		
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6			
67100100	MOBILIZATION	L SUM	1	1			
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1			
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1			
70102632	TRAFFIC CONTROL AND PROTECTION, STANDARD 701602	L SUM	1	1			
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1			
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1			
70300100	SHORT TERM PAVEMENT MARKING	FOOT	11252	11252			
70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SO FT	4114	4114			
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	99215	99215			
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	20326	20326			
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	728	728			
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	2936	2936			
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	1985	1985			
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	54740	54740			
*78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	4114	4114			

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	0005	0021		
*78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	99215	99215			
*78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	20326	20326			
*78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	728	728			
*78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	2936	2936			
*78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	1985	1985			
*78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	2529	2529			
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	2529	2529			
*81028200	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2" DIA.	FOOT	11		11		
*85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	1		1		
*87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	214		214		
*87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	228		228		
*87301900	ELECTRIC CABLE IN CONDUIT, EQUIPMENT GROUNDING CONDUCTOR, NO. 6 1C	FOOT	21		21		
*87500600	TRAFFIC SIGNAL POST, 10 FT.	EACH	1		1		
*87800100	CONCRETE FOUNDATION, TYPE A	FOOT	4		4		
*87900200	DRILL EXISTING HANDHOLE	EACH	1		1		
*88102717	PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	2		2		

*SPECIALTY ITEMS

FILE NAME =	USER NAME = normentor	DESIGNED -	REVISED -
PLT SCALE = 100.0000 "/ In.	CHECKED -	REVISION -	REVISION -
PLT DATE = 7/18/2014	DATE -	REVISION -	REVISION -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES		F.A.R. RTE. 330	SECTION (I&I)RS-3	COUNTY LAKE	TOTAL SHEETS 60	SHEET NO. 4
SCALE:	SHEET NO. OF SHEETS STA.	TO STA.		FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT CONTRACT NO. 60V03		