





RESTORATION OF WORK AREA, RESTORATION OF THE TRAFFIC SIGNAL WORK AREA SHALL BE INCLUDED IN THE RELATED PAY ITEM SUCH AS FOUNDATION, CONDUIT, HANDHOLE, TRENCH AND BACKFILL, ETC., AND NO EXTRA COMPENSATION SHALL BE ALLOWED. ALL ROADWAY SURFACES SUCH AS SHOULDERS, MEDIAN, SIDEWALKS, PAYEMENT ETC. SHALL BE REPLACED IN KIND. ALL DAMAGE TO MOWED LAWNS SHALL BE REPLACED WITH AN APPROVED SOD, AND ALL DAMAGE TO UNMOWED FIELDS SHALL BE SEEDED IN ACCORDANCE WITH STANDARD SPECIFICATIONS 252 AND 250 RESPECTIVELY.

FILE NAME =	USER NAME = _USERNAME_	DESIGNED	-	DW	REVISED	-	
N:\Projects3\0881-2039-00 IDOT PTB 148-0	4/13010 IL68 @ Portwine Rd/DesignCAD/Sheet I	ı Der sankank14_⊤	S-IL68-POR	RT WN E1.dgn	REVISED	-	
	PLOT SCALE = 20.0000 ' / in.	CHECKED	-	KMM	REVISED	-	
	PLOT DATE = \$DATE\$	DATE	-		REVISED	-	

STATE OF ILLINOIS							
DEPARTMENT	OF	TRANSPORTATION					

TRAFFIC SIGNAL MODERNIZATION PLAN ILLINOIS ROUTE 68 (DUNDEE ROAD) AND PORTWINE ROAD					SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
					1618TS	СООК	16	14
						CONTRACT	NO. 6	0X14
SCALE:	SHEET NO. 2 OF 2 SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT				