

URBAN

URBAN

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE 0005					
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	100% STATE 0005	80% STATE 20% VILLAGE OF VERNON HILLS 0031			
* K0012990	PERENNIAL PLANTS, ORNAMENTAL TYPE, GALLON POT	UNIT	6.6		6.6			
* A2002484	TREE, CARPINUS BETULUS FASTIGIATA, (COLUMNAR EUROPEAN HORNBEAM), 2" CALIPER, BALLED AND BURLAPPED	EACH	6		6			
* C2007765	SHRUB, ROSA RUGOSA 'FRAU DORAMARHARTOPP' (FRAU DAGMAR HASTRUP RUGOSA ROSE), CONTAINER GROWN, 5-GALLON	EACH	88		88			
XD327774	BACKFLOW PREVENTER (RPZ) 1.5 INCH	EACH	1		1			
* 21101615	TOPSOIL FURNISH AND PLACE, 4"	SO YD	463	463				
* 21101665	TOPSOIL FURNISH AND PLACE, 18"	SO YD	620		620			
* 21101805	COMPOST FURNISH AND PLACE, 2"	SO YD	620		620			
* 25200110	SODDING, SALT TOLERANT	SO YD	463	463				
31101200	SUBBASE GRANULAR MATERIAL, TYPE B 4"	SO YD	1080	1080				
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	196	196				
40600827	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	7162	7162				
40600895	CONSTRUCTING TEST STRIP	EACH	2	2				
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	599	599				
40603153	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, STONE MATRIX ASPHALT, N80	TON	12762	12762				
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX'D; N50	TON	13	13				
42001300	PROTECTIVE COAT	SO YD	347	347				
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SO YD	93	93				

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE 0005					
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	100% STATE 0005	80% STATE 20% VILLAGE OF VERNON HILLS 0031			
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SO FT	2278	2278				
42400800	DETECTABLE WARNINGS	SO FT	438	438				
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SO YD	130215	130215				
44000200	DRIVEWAY PAVEMENT REMOVAL	SO YD	203	203				
44000600	SIDEWALK REMOVAL	SO FT	2278	2278				
44201798	CLASS D PATCHES, TYPE I, 13 INCH	SO YD	300	300				
44201803	CLASS D PATCHES, TYPE II, 13 INCH	SO YD	2415	2415				
44201807	CLASS D PATCHES, TYPE III, 13 INCH	SO YD	683	683				
44201809	CLASS D PATCHES, TYPE IV, 13 INCH	SO YD	2245	2245				
56109210	WATER VALVES TO BE ADJUSTED	EACH	18	18				
56200700	WATER SERVICE LINE 2"	FOOT	20		20			
60109510	PIPE UNDERDRAINS, FABRIC LINED TRENCH 4"	FOOT	400		400			
60252800	CATCH BASINS TO BE RECONSTRUCTED	EACH	10	10				
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	120	120				
60406100	FRAMES AND LIDS, TYPE I, CLOSED LID	EACH	3	3				
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	1620	1620				

FILE NAME :	USER NAME : gpr20081110	DESIGNED -	REVISED -
C:\work\proj\hwy2008\1110\03565870\00224-31\plan.dgn		DRAWN -	REVISED -
PLOT SCALE = 1000000 / 1"		CHECKED -	REVISED -
PLOT DATE = 7/10/2014		DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES			
SCALE:	SHEET NO. OF SHEETS	STA. TO STA.	

F.A.P. RTE. 330	SECTION (282A1R5-10)	COUNTY LAKE	TOTAL SHEETS 42	SHEET NO. 3
CONTRACT NO. 60X23				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				

Rev.