

URBAN

URBAN

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE 0005					
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	100% STATE 0005	20% STATE VILLAGE OF VERNON HILLS 0031			
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SO FT	10040	10040				
60620000	CONCRETE MEDIAN, TYPE SB-6.24	SO FT	912	912				
* 66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	40	40				
* 66900450	SPECIAL WASTE PLANS AND REPORTS	L SUM	1	1				
* 66900530	SOIL DISPOSAL ANALYSIS	EACH	1	1				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6				
67100100	MOBILIZATION	L SUM	1	1				
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1				
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1				
70102632	TRAFFIC CONTROL AND PROTECTION, STANDARD 701602	L SUM	1	1				
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1				
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1				
70300100	SHORT TERM PAVEMENT MARKING	FOOT	6156	6156				
70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SO FT	2736	2736				
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	47101	47101				
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	12054	12054				

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE 0005					
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	100% STATE 0005	20% STATE VILLAGE OF VERNON HILLS 0031			
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	2088	2088				
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	3083	3083				
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	1196	1196				
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	28594	28594				
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	2736	2736				
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	47101	47101				
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	12054	12054				
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	2088	2088				
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	3083	3083				
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	1196	1196				
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	1910	1910				
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	1820	1820				
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	6462	6462				
* 89502376	REBUILD EXISTING HANDHOLE	EACH	2	2				
* A2007016	TREE, QUERCUS ROBUR FASTIGIATA (FASTIGIATE ENGLISH OAK), 2" CALIPER, BALLED AND BURLAPPED	EACH	5		5			
* K0012993	PERENNIAL PLANTS, ORNAMENTAL TYPE, 3-GALLON POT	UNIT	3.76		3.76			

FILE NAME	USER NAME	DESIGNED	REVISIONS
		DRAWN	REVISIONS
		CHECKED	REVISIONS
		DATE	REVISIONS

STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES		SECTION		COUNTY		TOTAL SHEET NO.	
SCALE:	SHEET NO. OF SHEETS STA. TO STA.	330	(2&2A)RS-10	LAKE	42	4	4
		CONTRACT NO. 60X23					
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT							

Rev.

\*Specialty Items