

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE
				CONT. MAINT. 100% STATE
				MINOR STRUCTURES
				0040
44000100	PAVEMENT REMOVAL	SQ YD	67	67
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	158	158
44201783	CLASS D PATCHES, TYPE IV, 11"	SQ YD	67	67
48101200	AGGREGATE SHOULDERS, TYPE B	TON	2	2
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1	1
50105220	PIPE CULVERT REMOVAL	FOOT	104	104
50200100	STRUCTURE EXCAVATION	CU YD	25	25
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	1277	1277
54002040	EXPANSION BOLTS 3/4 INCH X 6 INCH	EACH	27	27
54001001	BOX CULVERT END SECTION, CULVERT NO. 1	EACH	1	1
54003000	CONCRETE BOX CULVERTS	CU YD	9.1	9.1
54010402	PRECAST CONCRETE BOX CULVERTS 4' X 2'	FOOT	21	21
542A1060	PIPE CULVERTS, CLASS A, TYPE 2 15"	FOOT	33	33
542D0220	PIPE CULVERTS, CLASS D, TYPE 1 15"	FOOT	147	147
54213450	END SECTIONS 15"	EACH	8	8
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	1	1

12

FILE NAME =	USER NAME = woodshankr1	DESIGNED - RW	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
es:\ps_work\p\idat\woodshankr1\48362787	0366035-ent-details.dgn	DRAWN - RW	REVISED -			623	001	LASALLE	16	4	
	PLOT SCALE = 48.2808' / in.	CHECKED - HA	REVISED -			SCALE 20 SHEET 2 OF 3 SHEETS STA. TO STA.					
#MODELNAME#	PLOT DATE = 7/29/2014	DATE - 7/14/2014	REVISED -			ILLINOIS FED. AID PROJECT CONTRACT NO. 66035					

Rev.