

SCHEDULE CONTINUED

PAVEMENT MARKINGS																	
NOTE 1: 10' SKIP @ 40' OFFSET NOTE 2: 3' SKIP @ 12' OFFSET NOTE 3: CENTERLINE 4" - 4' @ 40 OFFSET NOTE 4: EDGE LINE: 4" - 4' @ 100' OFFSET			70300100		70301000	78004200	78004220	78004240	78004250	78004280		78009005		78009000	78009008	78009024	X7830072
			SHORT TERM PAVT MARKING CENTERLINE WHITE (NOTE 3) 2 APP. FOOT	SHORT TERM PAVT MARKING CENTERLINE YELLOW (NOTE 4) 1 APP. FOOT	WORK ZONE PAVT MARK REM 1 APP. SQ FT	PRE PLAST PAVT MARK, TY B - INLAID - LETTERS & SYMBOLS WHITE (NOTE 1 & 2) SQ FT	PRE PLAST PAVT MARK, TY B - INLAID - LINE 5" WHITE (NOTE 1 & 2) FOOT	PRE PLAST PAVT MARK, TY B - INLAID - LINE 8" WHITE FOOT	PRE PLAST PAVT MARK, TY B - INLAID - LINE 12" WHITE FOOT	PRE PLAST PAVT MARK, TY B - INLAID - LINE 24" WHITE FOOT	PRE PLAST PAVT MARK, TY B - INLAID - LINE 24" YELLOW FOOT	MOD URETH PAVT MARK - LINE 5" YELLOW MEDIAN FOOT	MOD URETH PAVT MARK - LINE 5" WHITE OUTSIDE FOOT	MOD URETH PAVT MARK- LETTERS & SYMBOLS WHITE SQ FT	MOD URETH PAVT MARK- LINE 8" WHITE FOOT	MOD URETH PAVT MARK- LINE 24" WHITE FOOT	GROOVE FOR RECESSED PAVT MARK 6" FOOT
LOCATION	LENGTH	AREA															
STATION TO STATION	FOOT	SQ FT															
I-55 SOUTHBOUND (A004)																	
STA 465+56.26 TO STA 534+84.73	6,928.47		1,385.69	277.14	323.33		1,732.12					6,928.47	6,928.47				13,856.94
STA 534+84.73 TO STA 541+90.61	705.88		141.18	28.24	32.94							705.88	882.35				
STA 541+90.61 TO STA 555+05.40	1,314.79		262.96	52.59	61.36		328.70					1,314.79	1,314.79				2,629.58
STA 555+05.40 TO STA 562+55.63	1,314.60		150.05	30.01	35.01							750.23	937.79				
STA 562+55.63 TO STA 575+70.23	1,314.60		262.92	52.58	61.35		328.65					1,314.60	1,314.60				2,629.20
STA 575+70.23 TO STA 577+98.08	227.85		45.57	9.11	10.63							227.85	284.81				
STA 577+98.08 TO STA 697+52.85	11,954.77		2,390.95	478.19	557.89		2,988.69					11,954.77	11,954.77				23,909.54
STA 697+52.85 TO STA 703+59.73	606.88		121.38	24.28	28.32							606.88	758.60				
STA 703+59.73 TO STA 735+32.73	3,173.00		634.60	126.92	148.07		793.25					3,173.00					3,173.00
STA 708+03.23 TO STA 728+63.06	2,059.83		411.97	82.39	96.13		514.96						2,059.83				2,059.83
STA 735+32.73 TO STA 790+97.12 BK	5,564.39		1,112.88	222.58	259.67		1,391.10					5,564.39	5,564.39				11,128.78
STA 184+93.00 AH TO STA 280+58.45	9,565.45		1,913.09	382.62	446.39		2,391.36					9,565.45	9,565.45				19,130.90
STA 280+58.45 TO STA 283+74.95	316.50		63.30	12.66	14.77							316.50	395.63				
STA 283+74.95 TO STA 456+47.79	17,272.84		3,454.57	690.91	806.07		4,318.21					17,272.84	17,272.84				34,545.68
STA 456+47.79 TO STA 457+68.22	120.43		24.09	4.82	5.62							120.43	150.54				
STA 457+68.22 TO STA 473+44.02	1,575.80		315.16	63.03	73.54								1,575.80				1,575.80
STA 457+68.22 TO STA 512+98.76	5,530.54		1,106.11	221.22	258.09		1,382.64					5,530.54					5,530.54
STA 485+27.64 TO STA 505+99.88	2,072.24		414.45	82.89	96.70								2,072.24				2,072.24
STA 512+98.79 TO STA 590+00.00	7,701.21		1,540.24	308.05	359.39		1,925.30					7,701.21	7,701.21				15,402.42
BUSINESS 55 INTERCHANGE																	
RAMP A (R101)																	
STA 00+00.00 TO STA 27+59.81	2,759.81			110.39	36.80							2,759.81	2,759.81				5,519.62
STA 27+59.81 TO STA 38+95.57	1,135.76			45.43	15.14								1,135.76				1,135.76
STA 27+59.81 TO STA 31+76.47	416.66		833.32		138.89			833.32									
STA 31+76.47 TO STA 38+95.57	719.10						179.78										
STA 1+38		24.33					24.33										
RAMP B (R102)																	
STA 00+00.00 TO STA 06+63.99	663.99			26.56	8.85								663.99				663.99
STA 06+63.99 TO STA 32+40.56	2,576.57			103.06	34.35							2,576.57	2,576.57				5,153.14
AROUND ISLAND	73.00												73.00				73.00
STA 00+00.00 TO STA 02+87.07	287.07						71.77										
STA 02+87.07 TO STA 06+63.99	376.92		753.84		125.64			753.84									
GORE CHEVERONS	153.91		153.91		25.65				153.91								
STA 29+37		24.33					24.33										
STA 30+62		24.33					24.33										
STA 31+67	20.50									20.50							
STA 31+77	18.50									18.50							
STA 31+45		15.6					15.60										
STA 31+50		15.6					15.60										
RAMP C (R103)																	
STA 00+00.00 TO STA 14+31.87	1,431.87			57.27	19.09							1,431.87	1,431.87				2,863.74
STA 14+31.87 TO STA 25+37.77	1,105.90			44.24	14.75								1,105.90				1,105.90
STA 14+31.87 TO STA 17+56.74	324.87		649.74		108.29			649.74									
STA 17+56.74 TO STA 25+37.77	781.03						195.26										
STA 1+38		24.33					24.33										

SCHEDULE CONTINUED ON NEXT SHEET

FILE NAME =	USER NAME = sparksgw	DESIGNED - DMS	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES				F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
Default	Default	DRAWN - DMS	REVISED -		SCALE: 1" = 100.0000' / 1" = 100.0000'	SHEET 15	OF	SHEETS	STA.	TO STA.	LOGAN	108	22
		CHECKED -	REVISED -								CONTRACT NO.	72D41	
		DATE -	REVISED -								ILLINOIS FED. AID PROJECT		