

PAVEMENT MARKINGS

NOTE 1: 10' SKIP @ 40' OFFSET  
 NOTE 2: 3' SKIP @ 12' OFFSET  
 NOTE 3: CENTERLINE 4" - 4" @ 40' OFFSET  
 NOTE 4: EDGE LINE: 4" - 4" @ 100' OFFSET

LOCATION	LENGTH	AREA	70300100		70301000	78004200	78004220	78004240	78004250	78004280		78009005		78009000	78009008	78009024	7830072
			SHORT TERM PAVT MARKING CENTERLINE WHITE (NOTE 3) 2 APP. FOOT	SHORT TERM PAVT MARKING CENTERLINE YELLOW (NOTE 4) 1 APP. FOOT	WORK ZONE PAVT MARK REM 1 APP. SQ FT	PRE PLAST PAVT MARK, TY B - INLAID - LETTERS & SYMBOLS WHITE SQ FT	PRE PLAST PAVT MARK, TY B - INLAID - LINE 5" WHITE (NOTE 1 & 2) FOOT	PRE PLAST PAVT MARK, TY B - INLAID - LINE 8" WHITE FOOT	PRE PLAST PAVT MARK, TY B - INLAID - LINE 12" WHITE FOOT	PRE PLAST PAVT MARK, TY B - INLAID - LINE 24" WHITE FOOT	PRE PLAST PAVT MARK, TY B - INLAID - LINE 24" YELLOW FOOT	MOD URETH PAVT MARK - LINE 5" YELLOW MEDIAN FOOT	MOD URETH PAVT MARK - LINE 5" WHITE OUTSIDE FOOT	MOD URETH PAVT MARK- LETTERS & SYMBOLS WHITE SQ FT	MOD URETH PAVT MARK- LINE 8" WHITE FOOT	MOD URETH PAVT MARK- LINE 24" WHITE FOOT	GROOVE FOR RECESSED PAVT MARK 6" FOOT
RAMP D (R104)																	
STA 00+00.00 TO STA 06+48.91	648.91			25.96	8.65								648.91				648.91
STA 06+48.91 TO STA 23+61.23	1,712.32			68.49	22.83						1,712.32	1,712.32					3,424.64
AROUND ISLAND	61.00											61.00					61.00
STA 00+00.00 TO STA 02+72.41	272.41					68.10											
STA 02+72.41 TO STA 06+48.91	376.50		753.00		125.50		753.00										
GORE CHEVERONS																	
STA 20+57		24.33				24.33			188.95								
STA 21+82		24.33				24.33											
STA 22+87	20.50									20.50							
STA 23+00	18.50									18.50							
STA 22+65		15.6				15.60											
STA 22+67		15.6				15.60											
ATLANTA INTERCHANGE																	
RAMP A (R201)																	
STA 00+00.00 TO STA 06+98.46	698.46			27.94	9.31							698.46					698.46
STA 06+98.46 TO STA 24+19.00	1,720.54			68.82	22.94						1,720.54	1,720.54					3,441.08
AROUND ISLAND	157.98													157.98			
STA 00+00.00 TO STA 03+56.74	356.74					89.19											
STA 03+56.74 TO STA 06+98.46	341.72		683.44		113.91		683.44										
GORE CHEVERONS																	
STA 21+44		24.33				24.33											
STA 22+70		24.33				24.33											
STA 23+74	18.00															18.00	
STA 23+82	18.00															18.00	
STA 23+54		15.6										15.60					
STA 23+48		15.6										15.60					
RAMP B (R202)																	
STA 00+00.00 TO STA 07+99.51	799.51			31.98	10.66						799.51	799.51					1,599.02
STA 07+99.51 TO STA 19+73.26	1,173.75			46.95	15.65							1,173.75					1,173.75
STA 07+99.51 TO STA 11+74.02	374.51		749.02		124.84		749.02										
STA 11+74.02 TO STA 19+73.26	799.24					199.81											
STA 1+34		24.33				24.33											
RAMP C (R203)																	
STA 00+00.00 TO STA 06+68.64	668.64			26.75	8.92							668.64					668.64
STA 06+68.64 TO STA 24+86.90	1,818.26			72.73	24.24						1,818.26	1,818.26					3,636.52
AROUND ISLAND	141.95													141.95			
STA 00+00.00 TO STA 02+96.28	296.28					74.07											
STA 02+96.28 TO STA 06+68.64	372.36		744.72		124.12		744.72										
GORE CHEVERONS																	
STA 22+14		24.33				24.33											
STA 23+39		24.33				24.33											
STA 24+50	18.00															18.00	
STA 24+48	18.00															18.00	
STA 24+22		15.6										15.60					
STA 24+19		15.6										15.60					
RAMP D (R204)																	
STA 00+00.00 TO STA 08+86.61	886.61			35.46	11.82						886.61	886.61					1,773.22
STA 08+86.61 TO STA 20+32.06	1,145.45			45.82	15.27							1,145.45					1,145.45
STA 08+86.61 TO STA 11+83.53	296.92		593.84		98.97		593.84										
STA 11+83.53 TO STA 20+32.06	848.53					212.13											
STA 1+55		24.33				24.33											
SUBTOTAL			49,954.07	7,933.88	10,970.31	354.36	41,998.15	12,294.72	642.91	1,329.00	264.00	178,169.80	181,437.26	62.40	299.93	72.00	347,318.33
TOTAL:			57,888		10,970	354	41,998	12,295	643	1,593		359,607		62	300	72	347,318