

INDEX OF SHEETS

- 1 COVER SHEET
- 2 SIGNATURES & SUMMARY OF QUANTITIES
- 3 WIDTH RESTRICTION SIGNING DETAIL
- 4-5 TRAFFIC CONTROL DETAILS
- 6-19 BRIDGE PLANS


HIGHWAY STANDARDS


- 701001-02
- 701006-05
- 701301-04
- 701321-13
- 701901-03
- 704001-07


GENERAL NOTES:

- 1. PROTECTIVE SHIELD SHALL BE ERECTED UNDER JOINT REMOVAL WORK AT PIERS 8, 10, & 13, UNLESS OTHERWISE DIRECTED BY THE ENGINEER. THE LIMITS OF THE PROTECTIVE SHIELD SHALL BE AS DIRECTED BY THE ENGINEER.
- 2. IDOT OPERATIONS SHALL BE NOTIFIED 21 DAYS PRIOR TO ANY WIDTH RESTRICTIONS TAKING PLACE.

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION
DIVISION OF HIGHWAYS
DISTRICT 6**

EXAMINED July 16th 20 14

 ENGINEER OF OPERATIONS

EXAMINED July 11 20 14

 ENGINEER OF PROJECT IMPLEMENTATION

EXAMINED July 9 20 14

 ENGINEER OF PROGRAM DEVELOPMENT

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE	
				0-01285-6001	0-01621-6017
				0014	0014
				S.N. 009-0001	S.N. 009-0001
50102400	CONCRETE REMOVAL	CU YD	23.7	23.7	
50157300	PROTECTIVE SHIELD	SQ YD	140	140	
50300255	CONCRETE SUPERSTRUCTURE	CU YD	24	24	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	4300	4300	
50800515	BAR SPLICERS	EACH	80	79	1
50800530	MECHANICAL SPLICERS	EACH	392	392	
52000110	PREFORMED JOINT STRIP SEAL	FOOT	33	33	
52000228	FINGER PLATE EXPANSION JOINT, 8"	FOOT	28	28	
52000230	FINGER PLATE EXPANSION JOINT, 9"	FOOT	28	28	
52000600	FABRIC REINFORCED ELASTOMERIC TROUGH	FOOT	60	60	
67100100	MOBILIZATION	L SUM	1	1	
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1	1	
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1	1	
70400100	TEMPORARY CONCRETE BARRIER	FOOT	1600	1600	
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	1600	1600	
70600240	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 2	EACH	4	4	
70600340	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 2	EACH	4	4	
X7200201	WIDTH RESTRICTION SIGNING	L SUM	1	1	
Z0001903	STRUCTURAL STEEL REMOVAL	POUND	6800	6800	
Z0034500	MODULAR EXPANSION JOINT 18"	FOOT	28	28	

20