

100% STATE

100% STATE

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	0011	
				SN 051-2008	
20200100	EARTH EXCAVATION	CU YD	640	640	
20300100	CHANNEL EXCAVATION	CU YD	510	510	
20400800	FURNISHED EXCAVATION	CU YD	280	280	
20700220	POROUS GRANULAR EMBANKMENT	CU YD	640	640	
21101505	TOPSOIL EXCAVATION AND PLACEMENT	CU YD	185	185	
25000350	SEEDING, CLASS 7	ACRE	0.4	0.4	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	80	80	
28000400	PERIMETER EROSION BARRIER	FOOT	1135	1135	
28100107	STONE RIPRAP, CLASS A4	SQ YD	257	257	
28200200	FILTER FABRIC	SQ YD	257	257	
31101200	SUBBASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	301	301	
35400300	PORTLAND CEMENT CONCRETE BASE COURSE WIDENING 8"	SQ YD	739	739	
35501324	HOT-MIX ASPHALT BASE COURSE, 10"	SQ YD	250	250	

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	0011	
				SN 051-2008	
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	20	20	
40600990	TEMPORARY RAMP	SQ YD	25	25	
40603315	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70	TON	105	105	
44000100	PAVEMENT REMOVAL	SQ YD	449	449	
44201815	CLASS D PATCHES, TYPE II, 14 INCH	SQ YD	12	12	
48203100	HOT-MIX ASPHALT SHOULDERS	TON	305	305	
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1	1	
50200450	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL FOR STRUCTURES	CU YD	515	515	
50800105	REINFORCEMENT BARS	POUND	62780	62780	
50800515	BAR SPLICERS	EACH	188	188	
51500100	NAME PLATES	EACH	1	1	
54003000	CONCRETE BOX CULVERTS	CU YD	284	284	