

URBAN

URBAN

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		0005 80% FEDERAL 20% STATE	0021 80% FEDERAL 20% STATE	0021 100% CITY
20200100	EARTH EXCAVATION	CU YD	236	236		
20400800	FURNISHED EXCAVATION	CU YD	181	181		
20800150	TRENCH BACKFILL	CU YD	389	389		
21101615	TOPSOIL FURNISH AND PLACE, 4"	SO YD	985	985		
28000500	INLET AND PIPE PROTECTION	EACH	9	9		
30300112	AGGREGATE SUBGRADE IMPROVEMENT 12"	SO YD	718	718		
40600990	TEMPORARY RAMP	SO YD	151	151		
40603545	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	460	460		
42000501	PORTLAND CEMENT CONCRETE PAVEMENT 10" (JOINTED)	SO YD	564	564		
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SO FT	3489	3489		
42400800	DETECTABLE WARNINGS	SO FT	38	38		
44000100	PAVEMENT REMOVAL	SO YD	88	88		
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SO YD	5472	5472		

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		0005 80% FEDERAL 20% STATE	0021 80% FEDERAL 20% STATE	0021 100% CITY
44000200	DRIVEWAY PAVEMENT REMOVAL	SO YD	856	856		
44000300	CURB REMOVAL	FOOT	5	5		
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	666	666		
44000600	SIDEWALK REMOVAL	SO FT	415	415		
44003100	MEDIAN REMOVAL	SO FT	330	330		
44004250	PAVED SHOULDER REMOVAL	SO YD	188	188		
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	1	1		
550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	FOOT	568	568		
55100700	STORM SEWER REMOVAL 15"	FOOT	601	601		
60218400	MANHOLES, TYPE A, 4' -DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	3	3		
60235700	INLETS, TYPE A, TYPE 3 FRAME AND GRATE	EACH	6	6		
60500040	REMOVING MANHOLES	EACH	1	1		
60500060	REMOVING INLETS	EACH	6	6		

* SPECIALTY ITEMS

FILE NAME =	USER NAME = steffennk	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.W. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
citywork\p\uidat\steffennk\08157683\1074282-ent-soq.dgn	DRAWN -	REVISED -	8379			(12)RIN	Effingham	36	3	
PLOT SCALE = 1/8" = 1'-0"	CHECKED -	REVISED -	CONTRACT NO. 74282							
PLOT DATE = 5/8/2014	DATE -	REVISED -	ILLINOIS FED. AID PROJECT							
Default				SCALE:	SHEET OF SHEETS	STA.	TO STA.			