

PAVEMENT MARKING SCHEDULE

LENGTH				SHORT TERM PAVEMENT MARKING	WORK ZONE PAVEMENT MARKING REMOVAL	PAVEMENT MARKING REMOVAL	GROOVING FOR RECESSED PAVEMENT MARKING, LETTERS, NUMBERS AND SYMBOLS	MODIFIED URETHANE PAVEMENT MARKING - LETTERS AND SYMBOLS	GROOVING FOR RECESSED PAVEMENT MARKING 5"	MODIFIED URETHANE PAVEMENT MARKING - LINE 4"	GROOVING FOR RECESSED PAVEMENT MARKING 7"	MODIFIED URETHANE PAVEMENT MARKING - LINE 6"	GROOVING FOR RECESSED PAVEMENT MARKING 9"	MODIFIED URETHANE PAVEMENT MARKING - LINE 8"	GROOVING FOR RECESSED PAVEMENT MARKING 13"	MODIFIED URETHANE PAVEMENT MARKING - LINE 12"	GROOVING FOR RECESSED PAVEMENT MARKING 25"	MODIFIED URETHANE PAVEMENT MARKING - LINE 24"	RAISED REFLECTIVE PAVEMENT MARKER	PRISMATIC CURB REFLECTORS
STATION		STATION	FEET	FT.	SQ. FT.	SQ. FT.	SQ. FT.	SQ. FT.	FT.	FT.	FT.	FT.	FT.	FT.	FT.	FT.	FT.	FT.	EACH	EACH
32+05	TO	33+61	156	109	12				780	780			32	32	44	44			10	
33+61	TO	35+25	164	796	88		46.8	46.8	491	491			324	324	33	33	33	33	20	
35+25	TO	36+71	146																	
36+71	TO	38+96	225	939	104		109.2	109.2	618	618	448	448				36	36	14	24	
38+96	TO	39+71	75	74	8		31.2	31.2	225	225	75	75							3	6
39+71	TO	42+50	279	711	80		62.4	62.4	806	806	223	223								28
EAST LEG OF RICKELMAN						220					180	180					41	41		
PROJECT TOTALS			1,045	2,629	292	220	249.6	249.6	2,920	2,920	926	926	356	356	77	77	110	110	47	58



PAVING SCHEDULE

STATION	TO	STATION	LENGTH FEET	WIDTH FEET	AREA SQ YD	BITUMINOUS MATERIALS (PRIME COAT) POUND	HOT MIX ASPHALT SURFACE REMOVAL 1 1/2" SQ YD	POLYMERIZED HOT MIX ASPHALT SURFACE COURSE, MIX "D", N90 TON	TEMPORARY RAMP SQ YD
32+05	TO	42+50	1,045	VAR.	5,472	2,462	5,472	460	151

EARTHWORK SCHEDULE

LOCATION	EARTH EXCAVATION CU. YD.	EXCAVATION TO BE USED IN EMBANKMENT ADJUSTED FOR SHRINKAGE CU. YD.	EMBANKMENT CU. YD.	EARTHWORK BALANCE WASTE(+) SHORTAGE(-) CU. YD.	TOPSOIL FURNISH AND PLACE 4" SQ. YD.
LT. STA. 36+15 TO 42+10	236	175	356	-181	985

FURNISHING AND ERECTING RIGHT OF WAY MARKERS
55.00' LT. STA. 41+49.20 1 EACH

PCC PAVEMENT 10"
LT. STA. 36+13 TO 40+69 564 S. Y.

PROTECTING OR RESETTING SURVEY MARKERS
60.00' LT. STA. 36+47.56 1 EACH
55.00' LT. STA. 36+75.00 1 EACH
55.00' LT. STA. 37+70.68 1 EACH
55.00' LT. STA. 39+75.00 1 EACH
45.00' LT. STA. 40+75.00 1 EACH
45.00' LT. STA. 41+00.00 1 EACH

COMB. CONC. CURB & GUTTER, TYPE B6.24
LT. STA. 36+15 TO 42+07 637 FEET

CONC. MEDIAN, TYPE SB-6.06 (DOWELLED)
STA. 36+71.5 TO 42+30.1 2776 S.F.