

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
				100% STATE	100% STATE
				ROADWAY 0005 RURAL	ROADWAY 0005 URBAN
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	288	50	238
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SO YD	341	69	272
40600990	TEMPORARY RAMP	SO YD	1565	335	1230
40603545	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	13415	3877	9538
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SO FT	5878		5878
42400800	DETECTABLE WARNINGS	SO FT	483		483
44000154	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/4"	SO YD	707		707
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SO YD	50103	28183	21920
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SO YD	64889	3328	61561
44000600	SIDEWALK REMOVAL	SO FT	5592		5592
44200120	PAVEMENT PATCHING, TYPE II, 10 INCH	SO YD	288	71	217
44200124	PAVEMENT PATCHING, TYPE III, 10 INCH	SO YD	131		131
44200126	PAVEMENT PATCHING, TYPE IV, 10 INCH	SO YD	1768	285	1483
44200970	CLASS B PATCHES, TYPE II, 10 INCH	SO YD	163	163	

FILE NAME =	USER NAME = ehollandeska	DESIGNED -	REVISED -
c:\pwork\pawdot\ehollandeska\d0305915\0875079-ah-500.dgn		DRAWN -	REVISED -
		CHECKED -	REVISED -
		DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
42	(139-1), 36-1, 110-1)RS-1	BOND	68	4
CONTRACT NO. 76679			ILLINOIS FED. AID PROJECT	