

PAVING SCHEDULE

LOCATION				HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	TEMPORARY RAMP	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/4"	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	STRIP REFLECTIVE CRACK CONTROL TREATMENT	AGGREGATE WEDGE SHOULDER, TYPE B	HOT-MIX ASPHALT SHOULDERS	PORTLAND CEMENT CONCRETE SURFACE REMOVAL, 1 1/4"	BITUMINOUS MATERIALS (PRIME COAT)	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)
STA.	TO	STA	DESCRIPTION / DISTANCE	(SQ YD)	(SQ YD)	(SQ YD)	(TON)	(SQ YD)	(SQ YD)	(SQ YD)	(FOOT)	(TON)	(TON)	(SQ YD)	(POUND)	(POUND)
			RURAL - IL 127 / IL 140													
500+28.00		527+12.37	2,684.37			23.3	1,182.0		7,939.2	1,692.6	5,368.7	75.0	36.2		129.3	4,221.4
			SN 003-0061			50.0										
528+60.32		539+48.48	1,088.16				456.5		3,283.2	339.7	2,176.3	49.1				1,630.3
			SN 003-0051			50.0										
542+67.56		550+65.59	798.03			30.2	335.2		1,949.9	710.3	1,596.1	33.5				1,197.0
			SN 003-0057			68.3										
553+42.98		555+18.72	175.74			25.0	73.8			585.7	351.5	3.1				263.6
			RURAL - IL 127													
450+22.54		452+94.54	272.00			48.9	104.1		634.4				53.3	1,238.9	285.5	557.5
244+65.00		289+29.19	4,464.19				1,714.0		14,376.2		8,017.0	127.0	104.5		373.4	6,001.8
			URBAN - IL 127													
53+67.16		79+46.00	2,578.84			79.6	1,039.6			8,244.7	1,444.1	27.3				3,713.0
79+46.00		94+35.00	1,489.00			106.7	904.4			7,092.7	2,969.9					3,230.1
94+35.00		140+28.00	4,593.00			253.0	2,479.2			19,662.0	9,193.7					8,854.5
140+28.00		172+68.66	3,240.66				1,605.2		13,691.0	147.0	6,414.1	64.4	156.7		559.5	5,362.0
			SN 003-0060			70.0										
174+14.63		225+91.98	5,177.35			483.1	2,681.3	706.8	8,229.1	17,676.8	5,663.4	23.5	650.9		2,299.7	9,602.3
228+91.11		244+65.00	1,573.89			87.6	784.1			8,738.1	1,482.8		316.9		1,131.7	2,800.5

BUTT JOINT SCHEDULE

STA.	SIDE	STA	DESCRIPTION / DISTANCE													
			RURAL - IL 127													
251+30.00	LT		ENTRANCE		32.8	6.5	2.8									44.3
252+50.00	LT		ENTRANCE		36.1	7.4	3.0									48.7
289+29.19	CL		END PROJECT	50.0		25.0	5.6									67.5
			URBAN - IL 127													
142+21.63	LT		LAKE DR	59.9		11.9	6.7									80.9
146+00.00	RT		ENTRANCE		41.3	8.0	3.5									55.8
147+10.00	RT		ENTRANCE		22.8	4.1	1.9									30.8
147+80.00	RT		ENTRANCE		51.2	9.5	4.3									69.1
148+34.00	LT		ENTRANCE		30.2	5.9	2.5									40.8
153+60.00	LT		ENTRANCE		63.8	13.9	5.4									86.1
165+38.54	LT		S IDLER LN	99.2		67.8	11.1									133.9
183+78.00	RT		ENTRANCE		26.8	5.3						2.3		36.2		
186+84.00	RT		ENTRANCE		35.6	7.1						3.0		48.1		
190+42.34	LT		BOWMAN INDUSTRIAL DR	41.4		16.6	4.6									55.9
	RT		BOWMAN INDUSTRIAL DR	37.0			4.1									50.0
TOTAL				288	341	1,565	13,415	707	50,103	64,890	44,678	403	1,324	1,239	4,863	48,198

ADA RAMP SCHEDULE

LOCATION	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	DETECTABLE WARNINGS	SIDEWALK REMOVAL	PEDESTRIAN RAILING	COMBINATION CURB AND GUTTER REMOVAL (SPECIAL)	CURB REMOVAL (SPECIAL)	CONCRETE CURB, TYPE B (SPECIAL)	COMBINATION CONCRETE CURB AND GUTTER, TYPE B (SPECIAL)
INTERSECTION / DESCRIPTION	(SQ FT)	(SQ FT)	(SQ FT)	(FOOT)	(FOOT)	(FOOT)	(FOOT)	(POUND)
URBAN - IL 127								
COLLEGE AVE / 4TH STREET	235.5	20.0	221.8		24.3			24.3
COLLEGE AVE / 3RD STREET	1,322.6	95.4	1,321.8	12.3		94.8	94.8	
3RD STREET / MAIN STREET	347.5	40.0	322.2			50.9	50.9	
3RD STREET / SOUTH STREET	1,103.7	74.0	1,138.3		110.3	16.0	16.0	114.9
3RD STREET / SUMMER AVENUE	355.2	32.0	337.1		28.3	30.9	25.9	33.3
3RD STREET / WINTER AVENUE	661.6	60.0	552.2		18.4	21.6	17.0	23.0
3RD STREET / SPRING STREET	407.3	34.0	361.9		9.3	13.3	13.3	9.3
3RD STREET / WASHINGTON AVENUE	600.8	56.0	522.3		50.5	20.0	45.9	24.6
3RD STREET / HARRIS STREET	224.5	20.0	231.2		18.0			18.0
HARRIS STREET / 2ND STREET	505.5	28.5	472.3		22.7			22.7
IL 127 / US 40	113.8	23.1	111.1					
TOTAL	5,878	483	5,592	12	282	248	264	270