

PAVEMENT PATCHING SCHEDULE								
LANE	STATION	LENGTH	WIDTH	AREA	PAVEMENT PATCHING, TYPE II, 10 INCH	PAVEMENT PATCHING, TYPE III, 10 INCH	PAVEMENT PATCHING, TYPE IV, 10 INCH	
		(FOOT)	(FOOT)	(SQ YD)	(SQ YD)	(SQ YD)	(SQ YD)	
NBR	450+21	25	10	27.8			27.8	
NBR	503+59	6	10	6.7	6.7			
NBR	505+33	6	10	6.7	6.7			
NBR	505+59	40	6	26.7			26.7	
SB	511+45	30	4	13.3	13.3			
SB	521+96	6	12	8.0	8.0			
NB	550+54	6	12	8.0	8.0			
SB	550+54	6	12	8.0	8.0			
SB	63+71	4	12	5.3	5.3			
SB	64+45	4	12	5.3	5.3			
NB	70+26	12	12	16.0		16.0		
NB	77+17	6	12	8.0	8.0			
NB	77+17	6	12	8.0	8.0			
SB	77+97	6	12	8.0	8.0			
SB	80+18	6	12	8.0	8.0			
NB	103+68	12	12	16.0		16.0		
NB	103+94	12	12	16.0		16.0		
NB	126+07	4	12	5.3	5.3			
NB	126+28	4	12	5.3	5.3			
NB	128+71	12	12	16.0		16.0		
NB	128+97	12	12	16.0		16.0		
SB	142+75	12	12	16.0		16.0		
NB	147+50	4	12	5.3	5.3			
SB	147+50	4	12	5.3	5.3			
NB	154+00	20	4	8.9	8.9			
NB	159+81	30	4	13.3	13.3			
SB	163+61	40	4	17.8		17.8		
NB	163+71	4	12	5.3	5.3			
SB	171+58	50	4	22.2			22.2	
SB	174+40	30	4	13.3	13.3			
SB	192+23	30	4	13.3	13.3			
NB	194+76	4	12	5.3	5.3			
SB	194+76	4	12	5.3	5.3			
SB	207+91	4	12	5.3	5.3			
SB	215+03	100	4	44.4			44.4	
SB	222+27	12	6	8.0	8.0			
SB	222+43	70	6	46.7			46.7	
NB	222+74	20	4	8.9	8.9			
NB	224+27	6	12	8.0	8.0			
NB	224+80	15	12	20.0			20.0	
SB	225+50	15	12	20.0			20.0	
SB	225+50	70	12	93.3			93.3	
NB	228+29	15	12	20.0			20.0	
NB	228+82	60	12	80.0			80.0	
SB	229+24	20	12	26.7			26.7	
SB	230+61	6	12	8.0	8.0			
NB	231+30	4	12	5.3	5.3			
SB	231+30	25	12	33.3			33.3	
SB	236+63	16	12	21.3			21.3	
SB	237+47	220	12	293.3			293.3	
SB	238+00	6	12	8.0	8.0			
SB	239+01	6	12	8.0	8.0			
SB	239+75	300	4	133.3			133.3	
NB	239+75	220	12	293.3			293.3	
NB	241+80	16	12	21.3			21.3	
NB	241+91	35	12	46.7			46.7	
SB	242+91	25	12	33.3			33.3	
NB	243+44	30	12	40.0			40.0	
SB	248+62	25	12	33.3			33.3	
NB	265+30	4	12	5.3	5.3			
SB	265+30	4	12	5.3	5.3			
NB	275+12	120	12	160.0			160.0	
SUBTOTAL					249.8	113.8	1,537.1	
ALLOWANCE FOR ANTICIPATED FAILURES 15%					37.5	17.1	230.6	
TOTAL					287	131	1,768	

* ALL STATION LOCATIONS ARE APPROXIMATE, ACTUAL LOCATIONS TO BE VERIFIED IN THE FIELD .

CLASS B PATCHING SCHEDULE									
LANE	STATION	LENGTH	WIDTH	TYPE II, 10 INCH	TYPE III, 10 INCH	TYPE IV, 10 INCH	SAW CUT (HMA SHLDR)	DOWEL BARS 1 1/2"	PAVEMENT FABRIC
		(FOOT)	(FOOT)	(SQ YD)	(SQ YD)	(SQ YD)	(FOOT)	(EACH)	(SQ YD)
NB	452+64	6	12	8.0			61.0	20.0	
SB	452+64	6	12	8.0			61.0	20.0	
NB	452+32	6	12	8.0			61.0	20.0	
SB	452+22	20	12			26.7	89.0	20.0	26.7
NB	452+16	6	12	8.0			61.0	20.0	
NB	451+90	6	12	8.0			61.0	20.0	
SB	451+90	6	12	8.0			61.0	20.0	
NB	451+74	6	12	8.0			61.0	20.0	
SB	451+74	10	12	13.3			69.0	20.0	
NB	451+37	16	12		21.3		81.0	20.0	21.3
SB	451+37	6	12	8.0			61.0	20.0	
NB	451+27	6	12	8.0			61.0	20.0	
SB	451+27	6	12	8.0			61.0	20.0	
NB	450+84	6	12	8.0			61.0	20.0	
NBR	450+84	6	12	8.0			61.0	20.0	
NBR	450+69	6	12	8.0			61.0	20.0	
NBR	450+42	6	12	8.0			61.0	20.0	
NBR	450+32	6	12	8.0			61.0	20.0	
SBR	450+32	6	12	8.0			61.0	20.0	
SUB TOTAL				141.3	21.3	26.7	1,215.0	380.0	48.0
ANTICIPATED FAILURES 15%				22.0	4.0	4.0	182.3	57.0	7.2
TOTAL				163	25	31	1,397	437	55

* ALL STATION LOCATIONS ARE APPROXIMATE, ACTUAL LOCATIONS TO BE VERIFIED IN THE FIELD.

TEMPORARY PAVEMENT MARKING SCHEDULE

STA.	TO	STA.	DESCRIPTION / DISTANCE	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS (SQ FT)	TEMPORARY PAVEMENT MARKING - LINE 4"				TEMPORARY PAVEMENT MARKING - LINE 8"	TEMPORARY PAVEMENT MARKING - LINE 12"	TEMPORARY PAVEMENT MARKING - LINE 24"	WORK ZONE PAVEMENT MARKING REMOVAL (SQ FT)				
					SOLID WHITE (FOOT)	DOTTED WHITE (FOOT)	SOLID YELLOW (FOOT)	SKIP DASH YELLOW (FOOT)	SOLID WHITE (FOOT)	SOLID WHITE (FOOT)	SOLID WHITE (FOOT)					
500+28		555+19	RURAL - IL 127 / IL 140 5,490.72	31.2				10,602.0		6,493.0	855.0	327.0	223.0	34.0	6,493.5	
450+23		452+95	RURAL - IL 127 272.00					636.0		532.0					389.4	
244+65		289+29	4,464.19 URBAN - IL 127					8,979.0		1,780.0	1,050.0				3,937.1	
53+67		94+35	4,067.84					7,772.0		5,845.0	492.0	127.0	776.0	93.0	5,750.6	
94+35		140+28	4,593.00	293.4				9,918.0		7,489.2	1,501.8		121.5	102.0	6,629.8	
140+28		174+15	3,386.63	44.0				3,668.0		7,267.0	311.0		713.5		4,462.9	
174+15		225+92	5,177.35	220.0				10,610.0	73.0	9,336.2	854.8		224.0	58.0	7,299.4	
225+92		244+65	1,873.02	26.4				3,671.0		3,443.0	50.0				2,388.5	
SUB-TOTAL								55,856.0	73.0	42,185.4	5,114.6					
TOTAL				615				103,229		454		2,058		287		37,351

SHORT TERM PAVEMENT MARKING SCHEDULE

STA	TO	STA	DISTANCE	SKIP DASH YELLOW (FOOT)	SKIP DASH WHITE (FOOT)
			RURAL - IL 127 / IL 140		
500+28		555+19	5,490.72	1,000.0	20.0
			RURAL - IL 127		
450+23		452+95	272.00	50.0	
244+65		289+29	4,464.19	815.0	
			URBAN - IL 127		
53+67		244+65	19,097.84	4,307.0	322.0
TOTAL				6,172	342