

IL 146 PAVEMENT MARKING SCHEDULE CONTINUED

STATION TO STATION	THERMOPLASTIC PAVEMENT MARKING					TEMPORARY			SHORT-TERM PAVEMENT MARKING	NOTES		
	4 INCH WHITE (EDGE LINE)	4 INCH YELLOW (SKIP-DASH)	4 INCH YELLOW (NPZ OR DBL)	6 INCH (CROSSWALK)	24 INCH (STOP BARS)	4 INCH	6 INCH	24 INCH				
	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT				
EQ STA 1625+29.34 (BK) = STA. 1625+31.55 (AH)												
LT & RT	1625+31.6	TO	1643+40.6	3620		3620			7240		543	
EQ STA 1643+40.63 (BK) = STA. 1643+63.79 (AH)												
LT & RT	1643+63.8	TO	1653+04.0	1882		1882			3764		282	
EQ STA 1653+03.96 (BK) = STA. 1652+88.05 (AH)												
LT & RT	1652+88.1	TO	1657+49.1	924		924			1848		138	
OMISSION - SN 076-0005 STA. 1657+49.13 TO STA. 1661+37.17												
LT & RT	1661+37.2	TO	1664+59.0	644		644			1288		97	
OMISSION - EX. LEVEE STA. 1664+59 TO STA. 1665+11												
LT & RT	1665+11.0	TO	1665+62.2	104	13				117		15	
LT	1665+11.0	TO	1665+62.2			52			52			
EQ STA 1665+62.18 (BK) = STA. 1667+09.59 (AH)												
LT & RT	1667+09.6	TO	1673+85.0	1352	169				1521		203	
LT	1667+09.6	TO	1673+85.0			676			676			
RT	1673+85.0							12		12	STOP BAR	
RT	1266+30.0							12		12	STOP BAR	
	MAIN ST.							12		12	STOP BAR	
	ADAMS ST.							12		12	STOP BAR	
	1673+87.0					80			80		CROSSWALK	
	1266+32.0					72			72		CROSSWALK	
	MAIN ST.					80			80		CROSSWALK	
	ADAMS ST.					72			72		CROSSWALK	
SUBTOTALS				96,404	6,847	64,792	304	48	168,043	304	48	15,008
TOTALS				168,043			304	48	168,043	304	48	15,008