MIXTURE REQUIREMENTS

LOCATION(S):	HOT-MIX ASPHALT SURFACE COURSE
MIXTURE USE(S):	HOT-MIX ASPHALT SURFACE COURSE, MIX C, N90
AC/PG:	PG64-22
RAP % (MAX):	SEE SPECIAL PROVISIONS
DESIGN AIR VOIDS:	4.0%, 90 GYRATION DESIGN
MIXTURE COMPOSITION: (GRADATION MIXTURE)	IL-9.5 MM
FRICTION AGGREGATE:	C SURFACE
QUALITY MANAGEMENT PROGRAM:	QCP

LOCATION(S):	INCIDENTAL HOT-MIX ASPHALT SURFACING
MIXTURE USE(S):	HOT-MIX ASPHALT SURFACE COURSE, MIX C, N90
AC/PG:	PG64-22
RAP % (MAX):	SEE SPECIAL PROVISIONS
DESIGN AIR VOIDS:	4.0%, 90 GYRATION DESIGN
MIXTURE COMPOSITION: (GRADATION MIXTURE)	IL-9.5 MM
FRICTION AGGREGATE:	C SURFACE
QUALITY MANAGEMENT PROGRAM:	QC/QA

LOCATION(S):	HOT-MIX ASPHALT LEVELING BINDER COURSE
MIXTURE USE(S):	HOT-MIX ASPHALT LEVELING BINDER, N90, IL-9.5MM FINE GRADE
AC/PG:	PGP64-22
RAP % (MAX):	SEE SPECIAL PROVISIONS
DESIGN AIR VOIDS:	4.0%, 90 GYRATION DESIGN
MIXTURE COMPOSITION: (GRADATION MIXTURE)	IL-9.5MM FINE GRADE
FRICTION AGGREGATE:	NONE
QUALITY MANAGEMENT PROGRAM:	QCP

LOCATION(S):	CLASS D PATCHING
MIXTURE USE(S):	HOT-MIX ASPHALT BINDER COURSE, N90, IL-19.0MM FINE GRADE
AC/PG:	PG64-22
RAP % (MAX):	SEE SPECIAL PROVISIONS
DESIGN AIR VOIDS:	4.0%, 90 GYRATION DESIGN
MIXTURE COMPOSITION: (GRADATION MIXTURE)	IL-19.0MM FINE GRADE
FRICTION AGGREGATE:	NONE
QUALITY MANAGEMENT PROGRAM:	QC/QA

STRUCTURE / MTD INFORMATION

SN & CENTERLINE STATION FAP ROUTE 726 (IL 37)	EXISTING FILL HEIGHT OVER BOX CULVERT	THICKNESS OF EXISTING PAVEMENT OVER BOX CULVERT	MTD CROSSING RESTRICTIONS
	FOOT	FOOT	
SN 077-7043 (STA 532+00)	8.0	0.91	PENDING
SN 077-7044 (STA 542+00)	5.4	0.91	LOADED
SN 077-2003 (STA 551+81)	1.5	0.67	PENDING
SN 077-7045 (STA 654+00)	8.0	0.91	PENDING
SN 077-7047 (STA 1853+00)	3.2	0.91	LOADED
SN 077-0021 (STA 1724+16)	BRIDGE	BRIDGE	PENDING