

CODE NO.	PAY ITEM DESCRIPTION	UNIT	URBAN TOTAL QUANTITY	ROADWAY 0004	BRIDGE 0011	LIGHTING 0021	TRAFFIC SIGNALS 0021		
							63RD ST/ YALE AVE	63RD ST/ WENTWORTH AVE	INTER- CONNECT
X0327618	LANDSCAPING, SPECIAL	L SUM	1	1					
* X0370082	STORM SEWER, TYPE 2, 8 INCH, EXTRA STRENGTH VITRIFIED CLAY PIPE (CDOT)	FOOT	98	98					
* X0370083	STORM SEWER, TYPE 2, 8 INCH, 4HP, CLASS 52 (CDOT) DUCTILE IRON PIPE	FOOT	113	113					
* X0370084	DRILL EXISTING MANHOLE OR HANDHOLE (CDOT)	EACH	28				14	14	
* X0370085	CLEAN EXISTING MANHOLE OR HANDHOLE (CDOT)	EACH	8				4	4	
* X0370076	ROD AND CLEAN DUCT IN EXISTING CONDUIT SYSTEM (CDOT)	FOOT	456				238	218	
* X0370082	BREAKDOWN STREET LIGHT FOUNDATION (CDOT)	EACH	6				3	3	
* X0370001	TRENCH AND BACKFILL WITH SCREENINGS (CDOT)	FOOT	312				42	39	231
* X0370086	CONCRETE FOUNDATION, 30" DIAMETER, 1 1/4" ANCHOR RODS, 17 1/4" BOLT CIRCLE, 9 FEET (CDOT)	EACH	1					1	
* X0370087	CONCRETE FOUNDATION, 30" DIAMETER, 1 1/2" ANCHOR RODS, 16 1/2" BOLT CIRCLE, 11 FEET (CDOT)	EACH	5				3	2	
* X0370088	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION (CDOT)	EACH	2				1	1	
* X0370089	TEMPORARY TRAFFIC SIGNAL INSTALLATION (CDOT)	EACH	2				1	1	
* X0370090	SIGNAL HEAD, POLYCARBONATE, LED, 3-SECTION, BRACKET MOUNTED (CDOT)	EACH	6				3	3	
* X0370091	SIGNAL HEAD, POLYCARBONATE, LED, 3-SECTION, MAST ARM MOUNTED (CDOT)	EACH	10				5	5	
* X0370092	SIGNAL HEAD, POLYCARBONATE, LED, 4-SECTION, BRACKET MOUNTED (CDOT)	EACH	2				1	1	
* X0370093	SIGNAL HEAD, POLYCARBONATE, LED, 4-SECTION, MAST ARM MOUNTED (CDOT)	EACH	2				1	1	
* X0370094	PEDESTRIAN SIGNAL HEAD, POLYCARBONATE, 1-FACE, LED, BRACKET MOUNTED, COUNTDOWN (CDOT)	EACH	4				2	2	
* X0370095	PEDESTRIAN SIGNAL HEAD, POLYCARBONATE, 2-FACE, LED, BRACKET MOUNTED, COUNTDOWN (CDOT)	EACH	4				2	2	
* X0370096	ELECTRIC CABLE IN CONDUIT, SIGNAL, NO. 14, 9/0 (CDOT)	FOOT	1,086				552	534	
* X0370097	MAST ARM, STEEL, MONOTUBE, 30 FOOT (CDOT)	EACH	1					1	
* X0370098	MAST ARM, STEEL, MONOTUBE, 35 FOOT (CDOT)	EACH	2				1	1	

■ NON-PARTICIPATING (100% STATE)  
 \* DENOTES SPECIALTY ITEM  
 ■ DENOTES CHICAGO DEPARTMENT OF TRANSPORTATION SPECIAL PROVISION

1:27:29 PM  
 5/22/2013

8501 N. Higgins Road Suite 280 Chicago, Illinois 60631 (773) 399-0112	USER NAME - 1485	DESIGNED - JSO	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	63rd STREET BRIDGE REPLACEMENT - COOK COUNTY SUMMARY OF QUANTITIES			F.A.T. RATE - 94	SECTION - 1920-B	COUNTY - COOK	TOTAL SHEETS - 137	SHEET NO. - 70
	PLOT SCALE - 1/8" = 1'-0"	CHECKED - THS	REVISED -		SCALE: NTS=0'	SHEET 7	OF 8 SHEETS	STA. TO STA.	CONTRACT NO. 60J15 ILLINOIS FED. AID PROJECT			
	PLOT DATE - 5/22/2013	DATE - 03-15-2013	REVISED -									

Rev.