

**KEY:**

- ADJ STRUCTURE TO BE ADJUSTED
- R STRUCTURE TO BE REMOVED
- 1 PROPOSED STRUCTURE
- 1 PROPOSED SEWER

STRUCTURE NO.	LOCATION		STRUCTURE TYPE	ELEVATION	
	STATION	OFFSET		RIM	INV
①	19+84.5	29.5' LT	CB, TY A, 4' DIA., TYPE 1 FRAME, OPEN LID (CITY OF CHICAGO)	599.92	594.75
②	19+87	29.5' RT	CB, TY A, 4' DIA., TYPE 1 FRAME, OPEN LID (CITY OF CHICAGO)	600.22	595.05
③	23+72	30' RT	CB, TY A, 4' DIA., TYPE 1 FRAME, OPEN LID (CITY OF CHICAGO)	600.41	595.24
④	23+69	29.5' LT	CB, TY A, 4' DIA., TYPE 1 FRAME, OPEN LID (CITY OF CHICAGO)	600.43	595.26


**NOTES:**

SEWER STRUCTURE RIMS ARE GIVEN AT THE FLOWLINE ELEVATIONS.

DRAINAGE STRUCTURES AND SEWER TO BE REMOVED WITHIN THE PROPOSED SEWER TRENCH ARE INCLUDED IN THE COST OF THE NEW SEWER, AND ARE NOT PAID FOR SEPARATELY.

PIPE NO.	LOCATION FROM STRUCTURE	SIZE & MATERIAL	LENGTH	SLOPE
①	① TO MAINLINE SEWER	STORM SEWER, TYPE 2, 8" ESVCP	36'	1%
②	② TO MAINLINE SEWER	STORM SEWER, TYPE 2, 8" ESVCP	38'	1%
③	③ TO MAINLINE SEWER	STORM SEWER, TYPE 2, 8" ESVCP	12'	1%
④	④ TO MAINLINE SEWER	STORM SEWER, TYPE 2, 8" ESVCP	12'	1%

9 FILES 5/21/2013 10:01:27 AM



USER NAME - 0756  
 DESIGNED - JSO  
 DRAWN - HJM  
 CHECKED - TNS  
 DATE - 03-15-2013

REVISED -  
 REVISED -  
 REVISED -  
 REVISED -

**STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION**

**63rd STREET BRIDGE REPLACEMENT - COOK COUNTY  
 DRAINAGE & UTILITIES**

SCALE: 1"=20' SHEET 1 OF 1 SHEETS STA. TO STA.

F.A.I. RTE. 94	SECTION 1920-B	COUNTY COOK	TOTAL SHEETS 137	SHEET NO. 20
CONTRACT NO. 60J15				
ILLINOIS FED. AID PROJECT				