

FILE NAME = SA\JOL\6300-6399\6346\028\Microa\CADD Sheets\0160677-sht-schedule.dgn

SUMMARY								
LOCATION	EARTH EXCAVATION 20200100	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE (15%)	EMBANKMENT	FURNISHED EXCAVATION	TOPSOIL EXCAVATION	TOPSOIL PLACEMENT (4")	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	TOPSOIL BALANCE WASTE (+) OR SHORTAGE (-)
				EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)				
	CU YD	CU YD	CU YD	CU YD	CU YD	CU YD	CU YD	CU YD
PRESTAGE								
COUNTY LINE ROAD (CLR)	155	132	0	132	0	0	0	0
TEMPORARY RAMP B	0	0	314	-314	98	98	0	0
TEMPORARY RAMP E	0	0	310	-310	195	195	0	0
SUBTOTAL	155	132	624	-491	293	293	0	0
STAGE I								
CLR SB ROADWAY & RAMPS	379	322	25	297	40	40	0	0
•CLR SW EMBANKMENT	18	15	552	-537	129	770	-641	-641
•CLR NW EMBANKMENT	60	51	123	-72	133	673	-540	-540
SUBTOTAL	457	388	700	-312	303	1,484	-1,182	-1,182
STAGE II								
CLR NB ROADWAY & RAMPS	394	335	129	206	66	66	0	0
•CLR NE EMBANKMENT	1	1	1,107	-1,106	109	632	-523	-523
•CLR SE EMBANKMENT	24	20	968	-948	46	626	-580	-580
SUBTOTAL	419	356	2,204	-1,849	221	1,324	-1,102	-1,102
STAGE III								
COUNTY LINE ROAD	455	387	0	387	0	0	0	0
TEMPORARY RAMP B	314	267	0	267	98	98	0	0
TEMPORARY RAMP E	310	263	0	263	195	195	0	0
SUBTOTAL	1,079	917	0	917	293	293	0	0
TOTAL QUANTITIES	2,109	1,793	3,528	-2,652	1,110	3,393	-2,284	-2,284

*NOTE: REQUIRED FOR BURR RIDGE'S LANDSCAPING IMPROVEMENTS.



1170 SOUTH HOUBOLT ROAD
JOLIET, ILLINOIS 60431
(815) 744-4200

USER NAME = dennissw
MODEL NAME = Default
PLOT SCALE = 100.0000' / in.
PLOT DATE = 1/30/2013

DESIGNED - MAG
DRAWN - DJW
CHECKED - DWG
DATE - 01-24-13

REVISED -
REVISED -
REVISED -
REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCALE: SHEET OF SHEETS STA. TO STA.

SCHEDULES

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	22-IHB-R	COOK/DUPAGE	161	19
CONTRACT NO. 60K77			ILLINOIS FED. AID PROJECT	