

EXISTING SIGN SCHEDULE														
LOCATION	DESCRIPTION	EXISTING LOCATION			EXISTING SIZE				REMOVE					
		STA.	OFFSET L/R	SUPPORT TYPE	WIDTH (FT)	HEIGHT (FT)	EXIT PANEL WIDTH (FT)	EXIT PANEL HEIGHT (FT)	REMOVE SIGN PANEL TYPE 1 (SQ FT)	REMOVE SIGN PANEL TYPE 3 (SQ FT)	REMOVE SIGN PANEL ASSEMBLY - TYPE A (SQ FT)	REMOVE SIGN PANEL ASSEMBLY - TYPE B (SQ FT)	REMOVE CONCRETE FOUNDATION - GROUND MOUNT (EACH)	REMOVE OVERHEAD SIGN STRUCTURE - BRIDGE MOUNT (EACH)
NB I-55	COOK COUNTY	999+50.00	88.0 RT	GROUND MOUNT	2	3					6			
NB I-56	COUNTY LINE ROAD EXIT	999+99.9	110.00 RT	I-BEAM	20.0	9.5	12	2	24	190			3	
SB I-55	COUNTY LINE ROAD EXIT	1002+71.5	95.00 LT	I-BEAM	20.0	9.5	12	2	24	190			3	
NB I-55	TRUCKS USE 2 RIGHT LANES	63+32.25	48.71 RT	BRIDGE MOUNT	10.00	4.00								1
SB I-55	TRUCKS USE 2 RIGHT LANES	64+97.00	48.57 RT	BRIDGE MOUNT	10.00	4.00								1
SB I-55	PACE BUS	SEE MOT PLANS		GROUND MOUNT	8.50	13.00						110.5		
RAMP H	DO NOT ENTER	54+15.60	79.13 LT	GROUND MOUNT	3.00	3.00					9			
RAMP H	DO NOT ENTER	54+25.80	39.31 LT	GROUND MOUNT	3.00	3.00					9			
RAMP H	WRONG WAY	54+94.21	111.04 LT	GROUND MOUNT	3.50	2.50					8.75			
RAMP E	DO NOT ENTER	401+45.67	22.29 LT	GROUND MOUNT	3.00	3.00					9			
RAMP E	DO NOT ENTER	401+46.96	13.93 RT	GROUND MOUNT	3.00	3.00					9			
RAMP E	WRONG WAY	400+46.77	14.34 RT	GROUND MOUNT	3.50	2.50					8.75			
RAMP E	WRONG WAY	400+44.38	25.58 LT	GROUND MOUNT	3.50	2.50					8.75			
RAMP B	DO NOT ENTER	201+52.04	27.73 RT	GROUND MOUNT	3.00	3.00					9			
RAMP B	DO NOT ENTER	201+54.54	10.96 LT	GROUND MOUNT	3.00	3.00					9			
RAMP B	WRONG WAY	203+33.00	14.55 LT	GROUND MOUNT	3.50	2.50					8.75			
RAMP B	WRONG WAY	203+33.00	28.11 RT	GROUND MOUNT	3.50	2.50					8.75			
RAMP D	DO NOT ENTER	75+97.61	48.74 RT	GROUND MOUNT	3.00	3.00					9			
RAMP D	DO NOT ENTER	76+06.16	84.96 RT	GROUND MOUNT	3.00	3.00					9			
RAMP D	WRONG WAY	74+27.01	106.85 RT	GROUND MOUNT	3.50	2.50					8.75			
RAMP D	WRONG WAY	74+39.38	137.36 RT	GROUND MOUNT	3.50	2.50					8.75			
TOTAL									48.00	380.00	139.25	110.50	6	2

FILE NAME = SA\JUL16300-6399\6346\028\Microa\CADD_Sheets\0160K77-sht-schedule.dgn



USER NAME = dennisw	DESIGNED - MAG	REVISED -
MODEL NAME = Default	DRAWN - DJW	REVISED -
PLOT SCALE = 100.0000' / 1in.	CHECKED - DWG	REVISED -
PLOT DATE = 1/30/2013	DATE - 01-24-13	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULES	
SCALE:	SHEET OF SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	22-1HB-R	COOK/DUPAGE	161	20
CONTRACT NO. 60K77			ILLINOIS FED. AID PROJECT	