


CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODES											
				INT. MAIN RECONSTRUCTION, NO ADDED CAPACITY		INT. MAIN BRIDGE REPLACEMENT, NO ADDED CAPACITY S.N. 016-0587		ITEP		INT. MAIN UNDERPASS LIGHTING		ITEP STREET LIGHTING		ITEP LANDSCAPING	
				90% FEDERAL 10% STATE		90% FEDERAL 10% STATE		80% FEDERAL 20% BURR RIDGE		90% FEDERAL 10% STATE		80% FEDERAL 20% BURR RIDGE		80% FEDERAL 20% BURR RIDGE	
				0004		0011		0011		0021		0021		0031	
URBAN		URBAN		URBAN		URBAN		URBAN		URBAN		URBAN			
COOK	DUPAGE	COOK	DUPAGE	COOK	DUPAGE	COOK	DUPAGE	COOK	DUPAGE	COOK	DUPAGE	COOK	DUPAGE		
* 25100115	MULCH, METHOD 2	ACRE	4											2	2
* 25100630	EROSION CONTROL BLANKET	SQ YD	14,766	2,391	2,390									4,993	4,992
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	419	35	34									175	175
28000305	TEMPORARY DITCH CHECKS	FOOT	192	96	96										
28000400	PERIMETER EROSION BARRIER	FOOT	5,396	535	535									2,163	2,163
28000510	INLET FILTERS	EACH	20	10	10										
28100105	STONE RIPRAP, CLASS A3	SO YD	44	22	22										
28200200	FILTER FABRIC	SO YD	44	22	22										
30300112	AGGREGATE SUBGRADE IMPROVEMENT 12"	SO YD	2,643	1,322	1,321										
31101200	SUBBASE GRANULAR MATERIAL, TYPE B 4"	SO YD	2,114	1,057	1,057										
31102300	SUBBASE GRANULAR MATERIAL, TYPE C 6"	SO YD	1,350											675	675
31200502	STABILIZED SUBBASE - HOT-MIX ASPHALT, 4 1/2"	SO YD	992	496	496										
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	9.2	4.6	4.6										
42000501	PORTLAND CEMENT CONCRETE PAVEMENT 10" (JOINTED)	SO YD	86	43	43										

FILE NAME : S:\101\_6388--6394\10345\1023\micron\c600 Sheets\0160677-11-500.dgn

\* SPECIALTY ITEM

 1170 SOUTH HOBOLT ROAD JOLIET, ILLINOIS 60431 (815) 744-4200	USER NAME : jshrkp	DESIGNED - MAG	REVISED -
	MODEL NAME : Default	DRAWN - DJW	REVISED -
	PLOT SCALE : 2.0000 1/1 in.	CHECKED - DWG	REVISED -
	PLOT DATE : 7/10/2013	DATE - 07-18-13	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES			
SCALE:	SHEET	OF	SHEETS

F.A.I. RTE.	SECTION	CO.	TOTAL SHEETS	SHEET NO.
55	22-IHB-R	COOK/DUPAGE	161	5
CONTRACT NO. 60K77			ILLINOIS FED. AID PROJECT	