

CONSTRUCTION TYPE CODES											
INT. MAIN		INT. MAIN		ITEP		INT. MAIN		ITEP		ITEP	
RECONSTRUCTION, NO ADDED CAPACITY		BRIDGE REPLACEMENT, NO ADDED CAPACITY		S. N. 016-0587		UNDERPASS LIGHTING		STREET LIGHTING		LANDSCAPING	
90% FEDERAL 10% STATE		90% FEDERAL 10% STATE		80% FEDERAL 20% BURR RIDGE		90% FEDERAL 10% STATE		80% FEDERAL 20% BURR RIDGE		80% FEDERAL 20% BURR RIDGE	
0004		0011		0011		0021		0021		0031	
URBAN		URBAN		URBAN		URBAN		URBAN		URBAN	
COOK	DUPAGE	COOK	DUPAGE	COOK	DUPAGE	COOK	DUPAGE	COOK	DUPAGE	COOK	DUPAGE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	COOK	DUPAGE	COOK	DUPAGE	COOK	DUPAGE	COOK	DUPAGE	COOK	DUPAGE
81100805	CONDUIT ATTACHED TO STRUCTURE, 3" DIA., PVC COATED GALVANIZED STEEL	FOOT	120							20	20	40	40
81300220	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 6" X 6" X 4"	EACH	16							8	8		
81300530	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 12" X 10" X 6"	EACH	18							4	4	5	5
81300550	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 12" X 12" X 6"	EACH	2	1	1								
81300800	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 18" X 12" X 6"	EACH	2							1	1		
81400200	HEAVY-DUTY HANDHOLE	EACH	2	1	1								
81603010	UNIT DUCT, 600V, 2-1C NO. 10, 1/C NO. 10 GROUND, (XLP-TYPE USE), 3/4" DIA. POLYETHYLENE	FOOT	1,878									939	939
81603047	UNIT DUCT, 600V, 3-1C NO. 6, 1/C NO. 6 GROUND, (XLP-TYPE USE), 1 1/4" DIA. POLYETHYLENE	FOOT	800									400	400
81603080	UNIT DUCT, 600V, 3-1C NO. 2, 1/C NO. 4 GROUND, (XLP-TYPE USE), 1 1/4" DIA. POLYETHYLENE	FOOT	1,772							886	886		
81702110	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 10	FOOT	6,423							2,022	2,021	1,190	1,190
81702150	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 2	FOOT	308									154	154
82107200	UNDERPASS LUMINAIRE, 100 WATT, HIGH PRESSURE SODIUM VAPOR	EACH	16							8	8		
82500350	LIGHTING CONTROLLER, BASE MOUNTED, 240VOLT, 100AMP	EACH	1									.5	.5
84200600	REMOVAL OF LIGHTING UNIT, NO SALVAGE	EACH	20							10	10		

* SPECIALTY ITEM

FILE NAME = S:\L\5280-ES\95145\028\Micro\1060 Sheets\018K77-sh-500.dgn



USER NAME = johnhp	DESIGNED - MAG	REVISED -
MODEL NAME = Default	DRAWN - DJW	REVISED -
PLOT SCALE = 2.0000' / 1"	CHECKED - DWG	REVISED -
PLOT DATE = 7/18/2013	DATE - 07-18-13	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET OF SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	CO.	TOTAL SHEETS	SHEET NO.
55	22-1HB-R	COOK/DUPAGE	161	14
CONTRACT NO. 60K77				
ILLINOIS FED. AID PROJECT				