



NOTES:

1. USE BLACK LETTERING ON ORANGE BACKGROUND.
2. ERECT SIGNS IN ADVANCE OF THE LOCATION FOR THE "ROAD CONSTRUCTION AHEAD" SIGN AT LOCATIONS AS DIRECTED BY THE ENGINEER.
3. ERECT SIGN ① WITH INSTALLED PANEL ② ONE WEEK PRIOR TO THE START OF CONSTRUCTION.
4. REMOVE PANEL ② SOON AFTER THE START OF CONSTRUCTION.
5. SEE SPECIAL PROVISION FOR "TEMPORARY INFORMATION SIGNING" FOR ADDITIONAL INFORMATION.
6. ONE SIGN ASSEMBLY EQUALS 25.70 SQ. FT. (2.3 SQ. M.)
7. SHALL BE PAID FOR AS TEMPORARY INFORMATION SIGNING.

ARTERIAL ROAD INFORMATION SIGN

LIN ENGINEERING LTD. Consulting Engineers Springfield, Illinois	USER NAME = *USER*	DESIGNED - SEW	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	DISTRICT STANDARDS US ROUTE 30 /IL 56 OVER IL 47		F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	PLOT SCALE = *SCALE*	DRAWN - SEW	REVISED -		573	61 HB-1-7	KANE	48	47		
	PLOT DATE = *DATE*	CHECKED - ST	REVISED -		SCALE: N/A		SHEET NO. 8 OF 9 SHEETS	STA.	TO STA.	TC-22	CONTRACT NO. 60N12
	DATE - 11/2011	REVISED -					FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		