

01 02
SUMMARY OF QUANTITIES

CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	S.N.	S.N.	0005 ROADWAY	CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	S.N.	S.N.	0005 ROADWAY
				045-0035	045-0036						045-0035	045-0036	
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	315	123	179	13	73304000	OVERHEAD SIGN STRUCTURE - BRIDGE MOUNTED	FOOT	13.5	13.5		
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	135	55	80		78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	77			77
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	605	246	359		78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	11132			11132
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	320	160	160		78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	155			155
48101620	AGGREGATE SHOULDERS, TYPE B 10"	SQ YD	129			129	78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	5819			5819
50102400	CONCRETE REMOVAL	CU YD	29.0	12.9	16.1		78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	395			395
50104650	SLOPE WALL REMOVAL	SQ YD	319	215	104		78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	149			149
50157300	PROTECTIVE SHIELD	SQ YD	898	383	515		78200530	BARRIER WALL MARKERS, TYPE C	EACH	264			264
50300100	FLOOR DRAINS	EACH	24	12	12		78300100	PAVEMENT MARKING REMOVAL	SO FT	8103			8103
50300255	CONCRETE SUPERSTRUCTURE	CU YD	29.2	13.0	16.2		78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	149			149
50300260	BRIDGE DECK GROOVING	SQ YD	1741	720	1021		X0326766	CLEAN & RESEAL RELIEF JOINT	FOOT	136	54	82	
50300300	PROTECTIVE COAT	SQ YD	424	205	219		X4400110	TEMPORARY PAVEMENT REMOVAL	SO YD	129			129
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	13570	11270	2300		X6060082	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.12 (SPECIAL)	FOOT	320	160	160	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	2620	1120	1500		X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1			1
50800515	BAR SPLICERS	EACH	48	24	24		X7030030	WET REFLECTIVE TEMPORARY TAPE TYPE III, 4 INCH	FOOT	13704			13704
51100100	SLOPE WALL 4 INCH	SO YD	319	213	106		X7030045	WET REFLECTIVE TEMPORARY TAPE TYPE III, 8 INCH	FOOT	6367			6367
52000110	PREFORMED JOINT STRIP SEAL	FOOT	166	70	96		Z0001800	APPROACH SLAB REPAIR (PARTIAL DEPTH)	SO YD	19	9	10	
52100020	ELASTOMERIC BEARING ASSEMBLY, TYPE II	EACH	30	12	18		Z0001899	JACK AND REMOVE EXISTING BEARINGS	EACH	30	12	18	
52100520	ANCHOR BOLTS, 1"	EACH	60	24	36		Z0001903	STRUCTURAL STEEL REMOVAL	POUND	9570	9570		
63301235	REMOVE AND REERECT STEEL PLATE BEAM GUARDRAIL, ATTACHED TO STRUCTURES	FOOT	48	24	24		Z0001905	STRUCTURAL STEEL REPAIR	POUND	10610	4790	5820	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6			6	Z0003600	BEAM STRAIGHTENING	L SUM	1	0.3	0.7	
67100100	MOBILIZATION	L SUM	1			1	Z0006020	BRIDGE DECK LATEX CONCRETE OVERLAY 3/2"	SQ YD	1807	755	1052	
70100207	TRAFFIC CONTROL AND PROTECTION, STANDARD 701402	EACH	2			2	Z0012152	BRIDGE DECK SCARIFICATION 3/2"	SO YD	1807	755	1052	
70100325	TRAFFIC CONTROL AND PROTECTION, STANDARD 701423	EACH	2			2	Z0012754	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SO FT	702	273	429	
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	6			6	Z0012755	STRUCTURAL REPAIR OF CONCRETE (DEPTH GREATER THAN 5 INCHES)	SO FT	77		77	
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	6			6	Z0016002	DECK SLAB REPAIR (FULL DEPTH, TYPE II)	SQ YD	54	24	30	
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	4			4	Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	280			280
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	8834			8834	Z0062456	TEMPORARY PAVEMENT	SO YD	129			129
70400100	TEMPORARY CONCRETE BARRIER	FOOT	1650.0			1650.0	Z0073300	TEMPORARY SHORING AND CRIBBING	L SUM	1	0.5	0.5	
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	1288			1288	Z0073351	TEMPORARY SLAB SUPPORT SYSTEM	L SUM	1	1		
70600260	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	4			4							
70600332	IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	4			4							
72000300	SIGN PANEL - TYPE 3	SO FT	94.5	94.5									

30
• DENOTES SPECIALTY ITEM