

PRINTED DATE: 7/12/2013
 FILE NAME: K:\P-Projects\DOT\8313\8313_Harlem over Maroon\Drawings\Sheet\83130712_Plan and Doc to IDOT\DOT\Sheet\83130712_Plan and Doc to IDOT.dwg

| SPECIALTY ITEM | CODE NUMBER | ITEM | UNIT | TOTAL QUANTITY | CONSTRUCTION TYPE CODE: 0014 SN: 016-2412 URBAN |
|----------------|-------------|-------------------------------------------------------------------------------|--------|----------------|-------------------------------------------------------|
| | 50102400 | CONCRETE REMOVAL | CU YD | 16.6 | 16.6 |
| | 50157300 | PROTECTIVE SHIELD | SQ YD | 320 | 320 |
| | 50300255 | CONCRETE SUPERSTRUCTURE | CU YD | 16.6 | 16.6 |
| | 50800205 | REINFORCEMENT BARS, EPOXY COATED | POUNDS | 2320 | 2320 |
| | 50800515 | BAR SPLICERS | EACH | 54 | 54 |
| | 52000110 | PREFORMED JOINT STRIP SEAL | FOOT | 119 | 119 |
| | 67000400 | ENGINEER'S FIELD OFFICE, TYPE A | CAL MO | 3 | 3 |
| | 67100100 | MOBILIZATION | LSUM | 1 | 1 |
| | 70106800 | CHANGEABLE MESSAGE SIGN | CAL MO | 2 | 2 |
| | 70301000 | WORK ZONE PAVEMENT MARKING REMOVAL | SQ FT | 2109 | 2109 |
| | 70400100 | TEMPORARY CONCRETE BARRIER | FOOT | 1200 | 1200 |
| | 70400200 | RELOCATE TEMPORARY CONCRETE BARRIER | FOOT | 1137.5 | 1137.5 |
| | 70600270 | IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, <i>WIDE</i>), TEST LEVEL 3 | EACH | 1 | 1 |
| | 70600330 | IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE, <i>WIDE</i>), TEST LEVEL 3 | EACH | 2 | 2 |
| | 7800020 | THERMOPLASTIC PAVEMENT MARKINGS- LINE 4" | FOOT | 1739 | 1739 |
| | 78008210 | POLYUREA PAVEMENT MARKING TYPE 1- LINE 4" | FOOT | 1636 | 1636 |
| | 78100100 | RAISED REFLECTIVE PAVEMENT MARKING | EACH | 26 | 26 |
| | 78100105 | RAISED REFLECTIVE PAVEMENT MARKING (BRIDGE) | EACH | 32 | 32 |
| | 78300100 | PAVEMENT MARKING REMOVAL | SQ FT | 625 | 625 |
| | 78300200 | RAISED REFLECTIVE PAVEMENT MARKER REMOVAL | EACH | 58 | 58 |
| | X7010216 | TRAFFIC CONTROL AND PROTECTION (SPECIAL) | LSUM | 1 | 1 |
| | X7030030 | WET REFLECTIVE TEMPORARY TAPE TYPE III, 4 INCH | FOOT | 6394 | 6394 |
| | Z0012754 | STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THEN 5 INCHES) | SQ FT | 1480 | 1480 |
| | Z0016001 | DECK SLAB REPAIR (FULL DEPTH, TYPE I) | SQ YD | 25 | 25 |
| | Z0016002 | DECK SLAB REPAIR (FULL DEPTH, TYPE II) | SQ YD | 20 | 20 |
| | Z0016200 | DECK SLAB REPAIR (PARTIAL) | SQ YD | 250 | 250 |
| | Z0030850 | TEMPORARY INFORMATION SIGNING | SQ FT | 25.7 | 25.7 |
| | Z0048665 | RAILROAD PROTECTIVE LIABILITY INSURANCE | LSUM | 1 | 1 |
| | Z0073200 | TEMPORARY SHORING AND CRIBBING | EACH | 8 | 8 |



| | |
|--------------------|---------------|
| USER NAME : *USER* | DESIGNED : JY |
| DRAWN : DN | REVISOR : |
| CHECKED : MR | REVISION : |
| DATE : 7/12/2013 | REVISION : |

| | |
|------------------|------------|
| DESIGNED : JY | REVISOR : |
| DRAWN : DN | REVISION : |
| CHECKED : MR | REVISION : |
| DATE : 7/12/2013 | REVISION : |

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

| | | | | |
|------------------------------|----------------|--------|--------------|----------|
| F.A.P. RTE | SECTION | COUNTY | TOTAL SHEETS | SHEET NO |
| 348 | 0708.3A-BR(11) | COOK | 25 | 3 |
| CONTRACT NO 60T07 | | | | |
| ILLINOIS FEDERAL AID PROJECT | | | | |

Rev