

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE										
				80% FED 20% STATE						80% FED 20% CITY		100% CITY		
				ROADWAY 0001	ROADWAY 0004	BRIDGE 0008	SAFETY 0021	RETAINING WALL 0040	RETAINING WALL 0040	OTHER 0044	SAFETY 0021	FACILITIES 0028	SAFETY 0021	
				URBAN	URBAN	081-0176	URBAN	081-7002	081-7003	URBAN	URBAN	URBAN		
30300112	AGGREGATE SUBGRADE IMPROVEMENT 12"	SO YD	2731		2731									
30300116	AGGREGATE SUBGRADE IMPROVEMENT 16"	SO YD	27857	6437	21420									
30300124	AGGREGATE SUBGRADE IMPROVEMENT 24"	SO YD	2321		2321									
31100500	SUBBASE GRANULAR MATERIAL, TYPE A 6"	SO YD	3211	3211										
31100910	SUBBASE GRANULAR MATERIAL, TYPE A 12"	SO YD	829		829									
31101400	SUBBASE GRANULAR MATERIAL, TYPE B 6"	SO YD	785									785		
35102000	AGGREGATE BASE COURSE, TYPE B 8"	SO YD	1261		1261									
35400500	PORTLAND CEMENT CONCRETE BASE COURSE WIDENING 10"	SO YD	362		362									
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	8	2	6									
40600300	AGGREGATE (PRIME COAT)	TON	14		14									
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	705		705									
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	221		221									
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SO YD	772		772									
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	294		294									

\* DENOTES SPECIALITY ITEM

FILE NAME: \\N:\PROJ\8003393\CONTRACT\1\Design\Misc\Sheets\025484.plt-50083.dgn



**Ciorba Group, Inc.**  
CONSULTING ENGINEERS  
5507 North Cumberland Avenue, Suite 402  
Chicago, Illinois 60659  
Tel. 773.776.4009 Fax 773.776.4014

USER NAME	• deloughlin	DESIGNED	-	REVISED	-
		DRAWN	-	REVISED	-
PLOT SCALE	• 100.0000 "/ IN.	CHECKED	-	REVISED	-
PLOT DATE	• 3/12/2013	DATE	• 3/12/2013	REVISED	-

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES				
SCALE:	SHEET NO.	OF	SHEETS	STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
595	(142-1R & 142-1HB)	ROCK ISLAND	507	5
CONTRACT NO. 64884				
ILLINOIS FED. AID PROJECT				