

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE									
				80% FED 20% STATE						80% FED 20% CITY		100% CITY	
				ROADWAY 0001	ROADWAY 0004	BRIDGE 0008	SAFETY 0021	RETAINING WALL 0040	RETAINING WALL 0040	OTHER 0044	SAFETY 0021	FACILITIES 0028	SAFETY 0021
				URBAN	URBAN	081-0176	URBAN	081-7002	081-7003	URBAN	URBAN	URBAN	URBAN
50300225	CONCRETE STRUCTURES	CU YD	376.2			221.1				155.1			
50300255	CONCRETE SUPERSTRUCTURE	CU YD	1395.1			428.1		424.5	542.5				
50300260	BRIDGE DECK GROOVING	SO YD	809			809							
50300285	FORM LINER TEXTURED SURFACE	SO FT	791						791				
50300300	PROTECTIVE COAT	SO YD	2875			1446		499	930				
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1			1							
50500505	STUD SHEAR CONNECTORS	EACH	2916			2916							
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	281190			146020		53970	81200				
50800515	BAR SPLICERS	EACH	96			96							
50901720	BICYCLE RAILING	FOOT	744			60		285	399				
50901735	BRIDGE FENCE RAILING (SIDEWALK)	FOOT	183			183							
50901750	PARAPET RAILING	FOOT	946			243		352	351				
51201610	FURNISHING STEEL PILES HP12X63	FOOT	320			320							
51202305	DRIVING PILES	FOOT	320			320							

\* DENOTES SPECIALITY ITEM

FILE NAME: c:\p\proj\1080391\08\constr\01\design\misc\sheet\08f484r-jat-5008e.dgn



**Ciorba Group, Inc.**  
CONSULTING ENGINEERS  
5507 North Cumberland Avenue, Suite 402  
Chicago, Illinois 60656  
Tel. 773.775.4009 Fax 773.775.4014

USER NAME * dsuwrnkh	DESIGNED -	REVISED -
PLOT SCALE * 1/8" = 1'-0"	DRAWN -	REVISED -
PLOT DATE * 3/11/2013	CHECKED -	REVISED -
	DATE * 3/11/2013	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. R.T.E.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
595	(142-1)R & 142-1)B	ROCK ISLAND	507	8
CONTRACT NO. 64B84			ILLINOIS FED. AIG PROJECT	