

42400200				
PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH				
STATION	LOCATION	LENGTH	WIDTH	SQ FT
41ST DRIVE CONNECTOR				
520+43	LT	14.8	6.0	88.8
520+43	LT	2.5	6.0	15.0
537+43	LT	14.8	6.0	88.8
537+43	LT	2.5	6.0	15.0
538+44	LT	14.8	6.0	88.8
538+44	LT	2.5	6.0	15.0
520+30	RT	22.5	13.3	299.3
520+43	RT	80.2	13.8	1,102.8
521+20	RT	13.0	12.3	159.9
521+33	RT	284.0	10.3	2,925.2
526+60	RT	34.0	11.5	391.0
526+94	RT	35.0	11.8	413.0
527+29	RT	99.0	10.7	1,059.3
527+28	RT	287.0	10.3	2,956.1
530+15	RT	20.0	12.9	258.0
531+05	RT	15.2	10.5	159.6
531+05	RT	5.0	11.0	55.0
534+21	RT	10.2	11.0	112.2
534+64	RT	14.0	11.0	154.0
537+41	RT	21.6	11.0	237.6
537+41	RT	4.0	11.0	44.0
538+45	RT	14.8	6.0	88.8
538+45	RT	2.5	6.0	15.0
41ST ST (AT 41ST AVE DRIVE)				
642+63	RT	8.0	4.0	32.0
COALTOWN RD				
13+93	LT	13.0	6.0	78.0
13+93	LT	2.5	6.0	15.0
14+92	LT	13.0	6.0	78.0
14+92	LT	2.5	6.0	15.0
21+78	LT	13.0	6.0	78.0
21+78	LT	2.5	6.0	15.0
22+47	LT	13.0	6.0	78.0
22+47	LT	2.5	6.0	15.0
21+71	RT	14.8	6.0	88.8
21+71	RT	2.5	6.0	15.0
22+66	RT	14.8	6.0	88.8
22+66	RT	2.5	6.0	15.0
TOTAL				11,354

42400800		
DETECTABLE WARNINGS		
STATION	LOCATION	SQ FT
41ST DRIVE CONNECTOR		
520+43	LT	10.0
537+53	LT	10.0
538+46	LT	10.0
520+25	RT	20.0
530+27	RT	20.0
531+00	RT	20.0
537+46	RT	20.0
538+43	RT	10.0
COALTOWN RD		
13+93	LT	10.0
14+92	LT	10.0
21+78	LT	10.0
22+47	LT	10.0
21+76	RT	10.0
22+61	RT	10.0
TOTAL		180

44000153		
HOT-MIX ASPHALT SURFACE REMOVAL, 1"		
STATION	STATION	SQ YD
EX 40TH AVENUE		
120+54	124+55	902.3
TOTAL		903

44000200		
DRIVEWAY PAVEMENT REMOVAL		
STATION	LOCATION	SQ YD
38TH STREET SOUTH		
155+75	LT	85.9
156+30	LT	15.1
156+60	LT	16.1
COALTOWN ROAD		
10+25	LT	51.7
16+00	RT	122.7
16+80	RT	85.3
20+20	LT	24.1
24+17	RT	109.6
27+15	RT	199.5
4ST AVENUE DRIVE		
187+00	RT	46.2
188+20	RT	64.9
193+85	LT	75.2
195+29	LT	63.4
35TH STREET		
6+20	LT	46.0
TOTAL		1,006

44000100		
PAVEMENT REMOVAL		
STATION	STATION	SQ YD
38TH STREET SOUTH		
MAINLINE		
589+75	593+36	975.5
593+36	596+86	1,591.0
ENTRANCE		
591+07		339.8
591+07		290.1
41ST AVENUE DRIVE		
MAINLINE		
538+23	539+00	578.5
539+00	540+66	938.5
39TH STREET		
MAINLINE		
140+00	141+60	428.2
COALTOWN ROAD/ 38TH STREET		
MAINLINE		
602+19	605+74	2,059.5
605+74	611+25	2,124.2
611+25	613+35	120.8
COALTOWN ROAD		
MAINLINE		
1+35	4+06	643.0
4+06	9+33	1,396.9
35TH STREET		
MAINLINE		
5+15	6+50	552.1
JOHN DEERE ROAD		
INTERSECTION		
2275+53	2277+28	547.8
41ST AVENUE DRIVE		
185+56	189+00	1,231.9
189+00	192+25	1,566.2
TOTAL		15,385

FILE NAME: c:\proj\080313\08\contract\1\design\misc\sheets\0264884-ant-sched13.dgn



Ciorba Group, Inc.
CONSULTING ENGINEERS
6507 North Cumberland Avenue, Suite 402
Chicago, Illinois 60656
Tel. 773.776.4009 Fax 773.776.4014

USER NAME = espino	DESIGNED -	REVISED -
	DRAWN -	REVISED -
PLOT SCALE = 2.0000' / IN.	CHECKED -	REVISED -
PLOT DATE = 3/11/2013	DATE - 3/11/2013	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.
--------	-----------	----	--------	------	---------

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
595	(142-1)R & 142-1)B	ROCK ISLAND	507	47
CONTRACT NO. 64B84				
ILLINOIS FED. AID PROJECT				