

44000500						
COMBINATION CURB AND GUTTER REMOVAL						
STATION	OFFSET	LOCATION	STATION	OFFSET	LOCATION	FOOT
44000500						
COMBINATION CURB AND GUTTER REMOVAL						
STATION	OFFSET	LOCATION	STATION	OFFSET	LOCATION	FOOT
38TH STREET						
151+11	74.4	LT	151+11	81.1	LT	6.8
151+35	75.6	LT	151+35	82.3	LT	6.8
150+74	14.6	RT	RADIUS			62.7
151+36	71.9	RT	RADIUS			83.5
154+58	19.1	LT	RADIUS			26.3
155+10	32.9	LT	RADIUS			225.7
154+20	43.2	RT	PARKING LOT			96.9
154+43	18.1	RT	155+94	27.9	RT	150.8
156+00	30.0	RT	157+44	30.0	RT	143.6
41ST DRIVE CONNECTOR						
532+12	38.5	LT	PARKING LOT			208.0
533+66	1.0	LT	RADIUS			162.8
532+47	6.0	RT	GUTTER			12.0
41ST AVENUE DRIVE						
185+56	13.4	RT	RADIUS			150.7
187+23	23.7	RT	RADIUS			88.3
189+13	17.3	RT	RADIUS			390.0
41ST STREET						
641+00	34.1	LT	643+00	34.3	LT	211.4
641+72	1.7	RT	643+00	8.3	LT	128.1
641+72	7.9	RT	643+00	8.3	RT	128.0
642+58	34.9	RT	642+67	34.9	RT	8.0
41ST AVENUE DRIVE						
538+45	15.0	LT	MEDIAN			58.3
538+39	106.6	LT	RADIUS			114.2
539+00	28.2	LT	RADIUS			98.1
538+20	61.8	RT	RADIUS			98.0
539+00	27.3	RT	RADIUS			173.6
540+15	49.5	LT	RADIUS			61.4
COALTOWN ROAD						
10+00	15.2	RT	13+75	24.0	RT	375.0
13+75	0.0	RT	19+14	61.9	RT	541.0
10+00	15.8	LT	13+75	115.4	LT	375.0
13+75	0.0	LT	18+18	140.5	LT	590.0
19+25	14.8	LT	24+75	0.5	LT	623.0
24+75	0.5	LT	26+54	14.2	LT	183.0
19+21	40.0	RT	22+33	259.0	RT	384.0
1+28	122.0	RT	4+06	16.0	RT	279.0
4+06	16.0	RT	4+72	16.0	RT	71.0
38TH STREET						
605+35	0.0	RT	MEDIAN			808.0
35TH SREET						
5+15	62.4	RT	RADIUS			264.0
TOTAL						
						7387

44000600				
SIDEWALK REMOVAL				
STATION	STATION	OFFSET	LOCATION	SO FT
41ST DRIVE CONNECTOR				
532+43	533+24	76.0	RT	566.8
533+45	534+29	7.0	LT	405.5
41ST STREET				
642+57		40.0	RT	32.4
COALTOWN ROAD				
21+80		90.0	LT	35.5
TOTAL				
				1,041

44003100		
MEDIAN REMOVAL		
STATION	STATION	SQ FT
41ST AVENUE DRIVE		
538+50	ISLAND	185.9
538+62	539+00	148.5
539+00	539+92	386.6
38TH STREET NORTH		
600+65	602+68	1,816.3
602+68	605+54	1,197.5
TOTAL		
		3,735

44004250					
PAVED SHOULDER REMOVAL					
STATION	LOCATION	STATION	LOCATION	SO YD	
38TH STREET SOUTH					
151+60	4.5 LT	153+35	0.0	LT	105.0
151+84	2.0 RT	154+30	403.0	RT	119.0
41ST AVENUE DRIVE					
185+56	6.3 LT	189+00	7.5	LT	263.7
189+00	7.5 LT	192+00	6.5	LT	233.3
TOTAL					
					721

44201717					
CLASS D PATCHES, TYPE II, 6 INCH					
STATION	STATION	LOCATION	LENGTH	WIDTH	SQ YD
41ST STREET					
642+57.6	642+65.4	LT	7.8	12.6	10.9
642+57.8	642+65.8	LT	8.0	13.9	12.4
642+58.0	642+66.0	RT	8.0	12.0	10.7
642+58.4	642+66	RT	8.0	13.2	11.7
EX 40TH AVE					
122+72.2	122+77.8	LT	5.6	9.0	5.6
122+72.3	122+77.7	RT	5.4	9.0	5.4
TOTAL					
					57

44201721						
CLASS D PATCHES, TYPE III, 6 INCH						
STATION	STATION	LOCATION	LENGTH	WIDTH 1	WIDTH 2	SQ YD
EX 40TH AVE						
120+54.0	120+88.7	LT	6.8	37.5	18.3	21.1
TOTAL						
						22

44201723						
CLASS D PATCHES, TYPE IV, 6 INCH						
STATION	STATION	LOCATION	LENGTH	WIDTH 1	WIDTH 2	SQ YD
38TH ST						
157+36.1	157+40.2	FULL WIDTH	4.0	59.4	59.4	26.4
TOTAL						
						27

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
595	(142-1)R & 142-1)B	ROCK ISLAND	507	48
CONTRACT NO. 64B84				
ILLINOIS FED. AID PROJECT				

FILE NAME: c:\proj\080313\08\contract\1\design\misc\sheets\0264884-ant-sched1.dgn



**Ciorba Group, Inc.**  
CONSULTING ENGINEERS  
6507 North Cumberland Avenue, Suite 402  
Chicago, Illinois 60656  
Tel. 773.776.4009 Fax 773.776.4014

USER NAME =	espino	DESIGNED -	REVISED -
		DRAWN -	REVISED -
PLOT SCALE =	2.0000' / IN.	CHECKED -	REVISED -
PLOT DATE =	3/11/2013	DATE -	3/11/2013
		REVISED -	