

PIPE CULVERTS SCHEDULE				542A4009	542D0220	542D1060	542D1069	542D1909	542D2755	542D5470	20800150
PIPE NO	FROM STR STA	TO STR STA	PIPE SLOPE	PIPE CULVERTS, CLASS A, TYPE 6 24"	PIPE CULVERTS, CLASS D, TYPE 1 15"	PIPE CULVERTS, CLASS D, TYPE 2 15"	PIPE CULVERTS, CLASS D, TYPE 2 24"	PIPE CULVERTS, CLASS D, TYPE 3 24"	PIPE CULVERTS, CLASS D, TYPE 4 30"	PIPE CULVERTS, CLASS D, TYPE 1 EORS 15"	TRENCH BACKFILL
				FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	CU YD
40TH AVENUE											
1	132+99 LT	133+16 LT	0.19%							16	
2	133+56 LT	133+78 LT	0.65%			20					
4	134+88 LT	135+11 LT	0.60%			20					
5	136+82 RT	136+69 LT	0.29%					90			57.4
6	136+69 LT	136+65 LT	0.29%				17				
7	121+09 RT	121+34 RT	0.30%							26	
8	121+72 RT	121+93 RT	0.38%							21	
9	122+26 RT	122+50 RT	0.16%							25	
10	122+75 RT	122+75 LT	0.46%		48						
11	123+31 RT	123+04 RT	0.25%							28	
12	123+87 RT	123+58 RT	2.62%							29	
41ST DRIVE CONNECTOR											
13	524+55 RT	524+50 LT	0.35%	96							
14	526+28 LT	526+40 RT	0.50%	165							0.6
15	527+50 LT	527+50 RT	0.14%						69		223.4
16	529+50 LT	529+50 RT	0.26%					78			178.5
TOTAL				261	48	40	107	78	69	145	460
TOTAL TRENCH BACKFILL FROM STORM SEWER SCHEDULE											987
TOTAL TRENCH BACKFILL											1447

FILE NAME: m:\proj\080319108\contract\1\design\misc\sheets\026484-shr\Sched16.dgn



Ciorba Group, Inc.
CONSULTING ENGINEERS
5507 North Cumberland Avenue, Suite 402
Chicago, Illinois 60656
Tel. 773.776.4009 Fax 773.776.4014

USER NAME = espino	DESIGNED -	REVISED -
	DRAWN -	REVISED -
PLOT SCALE = 2.0000' / IN.	CHECKED -	REVISED -
PLOT DATE = 3/11/2013	DATE - 3/11/2013	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULE OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
595	(142-1)R & 142-1HB	ROCK ISLAND	507	50
CONTRACT NO. 64B84				
ILLINOIS FED. AID PROJECT				