

DRAINAGE STRUCTURE SCHEDULE					INVERT ELEVATION				54213657	54261415	54261418	54261424	54261430	54263415	60204505
STR NO	STA	OFFSET	RIM ELEV	WEIR ELEV	N	S	E	W	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	CONCRETE END SECTION, STANDARD 542001, 15", 1:4	CONCRETE END SECTION, STANDARD 542001, 18", 1:4	CONCRETE END SECTION, STANDARD 542001, 24", 1:4	CONCRETE END SECTION, STANDARD 542001, 30", 1:4	CONCRETE END SECTION, STANDARD 542011, 15", 1:4	CATCH BASINS, TYPE A, 5'-DIA, TYPE 8 GRATE
									EACH	EACH	EACH	EACH	EACH	EACH	EACH
38TH STREET SOUTH															
1	149+74	21.67 R			566.56				1						
2	149+87	22.10 R	568.20		563.10	565.10	562.99	562.93							
3	150+74	19.73 R		566.85		563.29		563.29							
4	150+74	20.58 L		566.83	563.37		563.37								
5	151+60	38.52 L		566.74	563.55	563.55	563.65								
6	151+70	24.65 R		567.05				564.50							
7	151+95	32.00 L		566.98	563.62	563.62									
8	153+00	32.07 L		567.30	563.83	563.83	563.93								
9	153+00	27.27 R		567.32				564.75							
10	154+07	38.25 L	568.65		564.04	564.04	564.14								
11	154+61	71.18 R		567.71				564.74							
12	154+29	36.51 R		567.46	564.56			564.56							
13	154+44	60.28 L		567.16	564.11	564.11		564.11							
14	155+24	65.27 L		567.27	564.27		564.27								
15	154+68	76.63 R	568.29												
16	155+35	55.51 R		567.51				564.82							
17	155+46	40.99 L		567.71	564.33	564.33	564.33								
18	156+43	30.00 L	568.72		564.52	564.52	564.85								
19	156+43	20.61 R		568.54				565.11							
20	157+28	46.13 L	567.45			564.69	564.69								
21	157+41	11.63 R	567.51					564.81							
40TH AVENUE															
22	132+99	25.59 L					566.28								1
23	133+16	26.76 L						566.25							1
24	133+56	30.25 L					566.20			1					
25	133+78	32.28 L						566.07		1					
26	133+53	28.13 R						566.60		1					
27	133+84	32.62 R	568.92					566.50	566.50						
28	134+72	35.95 R	568.14					566.20	566.20						
29	134+88	39.25 L			565.66					1					
30	135+11	40.70 L				565.54				1					
31	135+40	59.74 R						565.98		1					
32	136+65	49.98 L						565.15			1				
33	136+69	31.83 L	573.73		565.30		565.20	565.20							
34	136+82	58.61 R						565.45			1				
35	121+09	17.11 R						566.64							1
36	121+34	17.02 R						566.56							1
37	121+72	17.33 R						566.43							1
38	121+93	17.56 R						566.35							1
39	122+26	17.86 R						566.29							1
40	122+50	17.63 R						566.25							1
41	122+75	35.36 L				565.80				1					
42	122+75	12.44 R			566.02					1					
43	123+04	16.93 R						566.09							1
44	123+31	17.22 R						566.16							1
45	123+58	17.00 R						566.24							1
46	123+87	17.00 R						567.00							1
41ST AVENUE DRIVE															
47	185+75	25.95 L		577.01		571.85									
48	185+75	14.00 R		577.25	571.63		571.63								
49	188+65	14.00 R		576.21	572.13		570.18	570.18							
50	188+65	26.00 L		575.97		572.35									
51	189+90	14.00 R		575.70	571.62		569.57	569.57							
52	189+90	26.00 L		575.46		571.84									
53	191+00	14.00 R		576.02	571.94		569.06	569.06							
54	191+00	26.00 L		575.78		572.16									
55	192+09	17.60 R	577.35		568.56	568.56									
56	193+45	14.00 R		575.78	567.92	567.92	571.44								
57	193+45	26.00 L		575.53				571.66							
58	195+08	21.61 R	574.31		567.12		567.12								
SUBTOTAL									1	8	0	2	0	12	0

NOTES:

1. STA AND OFFSET FOR INLETS ARE AT THE CENTER POINT ON THE FACE OF INLET.
2. STA, OFFSET AND ELEVATION FOR MANHOLES ARE AT THE CENTER OF THE STRUCTURE.
3. STA, OFFSET AND ELEVATION FOR FLARED END SECTIONS ARE AT THE CONNECTION TO THE STORM SEWER.

FILE NAME: c:\proj\0803193\08\contract\1\design\misc\sheets\0264884-ant-sched17.dgn



Ciorba Group, Inc.
 CONSULTING ENGINEERS
 5507 North Cumberland Avenue, Suite 402
 Chicago, Illinois 60656
 Tel. 773.776.4009 Fax 773.776.4014

USER NAME = espino	DESIGNED -	REVISED -
	DRAWN -	REVISED -
PLOT SCALE = 2.0000' / IN.	CHECKED -	REVISED -
PLOT DATE = 3/11/2013	DATE - 3/11/2013	REVISED -

**STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION**

SCHEDULE OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
595	(142-1)R & 142-1)B	ROCK ISLAND	507	51
CONTRACT NO. 64B84				
ILLINOIS FED. AID PROJECT				