

DRAINAGE STRUCTURE SCHEDULE (CON'T.)					INVERT ELEVATION				54213657	54261415	54261418	54261424	54261430	54263415	60204505
STR NO	STA	OFFSET	RIM ELEV	WEIR ELEV	N	S	E	W	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	CONCRETE END SECTION, STANDARD 542001, 15", 1:4	CONCRETE END SECTION, STANDARD 542001, 18", 1:4	CONCRETE END SECTION, STANDARD 542001, 24", 1:4	CONCRETE END SECTION, STANDARD 542001, 30", 1:4	CONCRETE END SECTION, STANDARD 542011, 15", 1:4	CATCH BASINS, TYPE A, 5'-DIA, TYPE 8 GRATE
									EACH	EACH	EACH	EACH	EACH	EACH	
59	195+08	26.08 L		573.82			566.88	566.88							
60	195+63	30.04 L	574.40		566.58	566.58									
61	196+80	34.00 R	572.24				566.36								
62	196+80	42.46 L		571.71	565.96		565.96	565.96							
63	197+70	40.2 R	571.17				567.18								
64	198+19	37.90 R	570.84				567.18								
65	198+51	34.44 L		570.39	565.65		565.65	566.63							
66	198+60	28.00 R		570.49			566.88	566.88							
67	199+27	38.01 R		570.90	566.55			566.55							
68	199+35	51.28 L		571.11		566.09	565.27	565.27							
69	642+63	83.34 R					564.25					1			
41ST DRIVE CONNECTOR															
70	521+05	66.56 L					578.10	1							
71	521+05	52.57 L	586.65				578.30	582.75							
72	521+05	15.54 R	593.06			587.90	587.80								
73	521+05	27.08 L		592.49			587.23	587.33							
74	521+05	19.13 R	593.12												
75	522+20	17.58 R	593.91												
76	522+20	14.00 R	593.86		589.00		589.10								
77	522+20	25.98 L	593.62					589.50							
78	524+50	41.42 L						566.91				1			
79	524+55	50.79 R					567.25					1			
80	526+28	64.20 L						566.28				1			
81	526+40	90.47 R					565.45					1			
82	527+50	22.58 L						569.40					1		
83	527+50	45.73 R					569.30						1		
84	527+78	30.58 R	589.04												
85	527+83	14.51 L	586.92					581.91							
86	527+83	27.00 R	586.66			581.39	581.49								
87	529+43	34.12 R	580.24												
88	529+43	30.53 R	580.19		575.31	574.25	574.35								
89	529+43	18.53 L	580.42					574.60							
90	529+50	27.29 L						565.00				1			
91	529+50	51.27 R					564.80					1			
92	530+00	36.73 R	577.76												
93	530+03	33.77 R	577.56		569.96	569.86									
94	531+13	20.00 L	573.65			566.62									
95	531+03	42.89 R	573.34		566.30		566.30								
96	531+86	23.71 R	571.69			565.84	565.84	565.84							
97	531+84	50.60 R			565.80							1			
98	532+35	20.99 R		570.28	565.91		565.91	565.91							
99	532+35	21.00 L		570.28		566.05									
100	532+83	33.19 L	568.29		565.21		566.12								1
101	533+03	21.08 R		569.79	566.02		566.02	566.02							
102	533+03	21.00 L		569.79		566.09		566.09							
103	533+96	21.00 R		569.51	566.44			566.44							
104	533+96	21.00 L		569.51		566.53	566.53								
105	534+22	31.09 L		569.21				566.59							
106	534+96	26.70 L		569.07			565.46								
107	535+10	21.53 L		569.15		565.39		565.39							
108	535+10	27.65 R		569.48	565.13		565.13								
109	536+00	33.00 R		568.50	564.68		564.68	564.68							
110	536+00	21.00 L		568.74		565.00									
111	536+90	33.00 R		567.61			564.23	564.23							
COAL TOWN ROAD															
112	11+10	15.44 L		591.11		587.25	587.15								
113	11+10	19.12 R		591.04	587.42										
114	11+90	28.63 R		591.58	587.92										
115	11+90	17.44 L		591.80		587.67	586.65	586.75							
116	13+35	21.00 L		592.93		585.85		585.95							
SUBTOTAL									1	0	0	8	2	0	1

NOTES:  
1. STA AND OFFSET FOR INLETS ARE AT THE CENTER POINT ON THE FACE OF INLET.  
2. STA, OFFSET AND ELEVATION FOR MANHOLES ARE AT THE CENTER OF THE STRUCTURE.  
3. STA, OFFSET AND ELEVATION FOR FLARED END SECTIONS ARE AT THE CONNECTION TO THE STORM SEWER.

FILE NAME: c:\p\proj\08031910\con\act\1\design\misc\sheet\0264884-ant\Sched18.dgn



**Ciorba Group, Inc.**  
CONSULTING ENGINEERS  
6507 North Cumberland Avenue, Suite 402  
Chicago, Illinois 60656  
Tel. 773.776.4009 Fax 773.776.4014

USER NAME = espino	DESIGNED -	REVISED -
	DRAWN -	REVISED -
PLOT SCALE = 2.0000' / IN.	CHECKED -	REVISED -
PLOT DATE = 3/11/2013	DATE - 3/11/2013	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**SCHEDULE OF QUANTITIES**

SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.
--------	-----------	----	--------	------	---------

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
595	(142-1)R & 142-1)B	ROCK ISLAND	507	52
CONTRACT NO. 64B84				
ILLINOIS FED. AID PROJECT				