

STORM SEWER SCHEDULE				550A0050	550A0070	550A0120	550A0340	550A0360	550A0380	550A0410	Z0056608	Z0056610	Z0056616	60107600	20800150
PIPE NO	FROM STR STA	TO STR STA	PIPE SLOPE	STORM SEWERS, CLASS A, TYPE 1 12"	STORM SEWERS, CLASS A, TYPE 1 15"	STORM SEWERS, CLASS A, TYPE 1 24"	STORM SEWERS, CLASS A, TYPE 2 12"	STORM SEWERS, CLASS A, TYPE 2 15"	STORM SEWERS, CLASS A, TYPE 2 18"	STORM SEWERS, CLASS A, TYPE 2 24"	STORM SEWER (WATER MAIN REQUIREMENTS) 12 INCH	STORM SEWER (WATER MAIN REQUIREMENTS) 15 INCH	STORM SEWER (WATER MAIN REQUIREMENTS) 24 INCH	PIPE UNDERDRAINS 4"	TRENCH BACKFILL
				FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT
38TH STREET SOUTH															
1	149+74 RT	149+87 RT	18.25%	8											
2	149+87 RT	150+74 RT	0.24%			79									
3	150+74 RT	150+74 LT	0.20%			41									
4	150+74 LT	151+60 LT	0.22%			83									
5	151+60 LT	151+95 LT	0.25%			28									
6	151+70 RT	151+60 LT	1.33%								64				1.1
7	153+00 LT	151+95 LT	0.21%			98									
8	151+60 LT	154+07 LT												250	
9	151+70 RT	154+00 RT												250	
10	153+00 RT	153+00 LT	1.37%								60				1.9
11	153+00 LT	154+07 LT	0.20%			103									
12	154+61 RT	154+29 RT	0.56%	39											1.5
13	154+29 RT	154+07 LT	0.55%								76				6.3
14	154+44 LT	154+07 LT	0.18%						38						2.6
15	155+24 LT	154+44 LT	0.21%									78			1.4
16	155+24 LT	154+44 LT												82	
17	155+46 LT	155+24 LT	0.25%		24										0.9
18	154+61 RT	155+35 RT												80	
19	155+35 RT	155+46 LT	0.52%								94				3.7
20	155+35 RT	156+43 RT												120	
21	156+43 LT	155+46 LT	0.20%	94											
22	156+43 RT	156+43 LT												53	
23	155+46 LT	156+43 LT												100	
24	156+43 RT	156+43 LT	0.51%	51											3.9
25	157+28 LT	156+43 LT	0.20%	84											
26	157+41 RT	157+28 LT	0.20%	60											
40TH AVENUE															
27	133+53 RT	133+84 RT	0.30%		33										
28	133+84 RT	134+72 RT	0.32%									95			
29	134+72 RT	135+40 RT	0.27%					81							
30	530+03 RT	136+69 LT	7.60%				60								48.0
41ST AVENUE DRIVE															
31	185+75 LT	185+75 RT	0.54%				41								11.7
32	185+75 LT	188+65 RT	0.51%				283								93.9
33	188+65 LT	188+65 RT	0.54%				41								5.1
34	185+75 RT	187+00 RT												122	
35	187+00 RT	188+65 RT												164	
36	185+75 LT	187+00 LT												121	
37	187+00 LT	188+65 LT												166	
38	188+65 RT	189+90 RT												120	
39	188+65 LT	189+90 LT												125	
40	188+65 RT	189+90 RT	0.52%					117							43.4
41	189+90 LT	189+90 RT	0.54%				41								9.5
42	189+90 LT	189+90 RT												44	
43	189+90 RT	191+00 RT	0.54%						95						
44	189+90 LT	192+10 LT												245	
45	189+90 RT	192+10 RT												210	
46	191+00 LT	191+00 RT	0.54%				41								5.1
47	191+00 RT	192+09 RT	0.52%						96						
48	192+10 LT	193+45 LT												138	
49	192+10 RT	193+45 RT												127	
50	192+09 RT	193+45 RT	0.52%						122						
51	193+45 LT	193+45 RT	0.54%				41								31.3
52	193+45 RT	195+08 RT												159	
53	193+45 LT	195+08 LT												163	
54	193+45 RT	195+08 RT	0.52%							154					
55	195+08 RT	195+08 LT	0.55%							44					30.9
56	195+08 LT	195+63 LT	0.53%										57		43.7
57	195+08 RT	196+80 RT												158	
58	195+08 LT	196+80 LT												182	
59	195+63 LT	196+80 LT	0.50%							123					54.8
SUBTOTAL				336	57	432	548	198	351	321	294	173	57	3179	400.8

FILE NAME: c:\p\proj\080313\08\contract\1\design\misc\sheets\026484-ant\Sched23.dgn



Ciorba Group, Inc.
CONSULTING ENGINEERS
5507 North Cumberland Avenue, Suite 402
Chicago, Illinois 60656
Tel. 773.776.4009 Fax 773.776.4014

USER NAME = espino	DESIGNED -	REVISED -
PLOT SCALE = 2.0000' / IN.	DRAWN -	REVISED -
PLOT DATE = 3/11/2013	CHECKED -	REVISED -
	DATE - 3/11/2013	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULE OF QUANTITIES

SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.
--------	-----------	----	--------	------	---------

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
595	(142-1)R & 142-1)B	ROCK ISLAND	507	57
CONTRACT NO. 64B84				
ILLINOIS FED. AID PROJECT				