

STORM SEWER SCHEDULE (CON'T.)				550A0050	550A0070	550A0120	550A0340	550A0360	550A0380	550A0410	Z0056608	Z0056610	Z0056616	60107600	20800150
PIPE NO	FROM STR STA	TO STR STA	PIPE SLOPE	STORM SEWERS, CLASS A, TYPE 1 12"	STORM SEWERS, CLASS A, TYPE 1 15"	STORM SEWERS, CLASS A, TYPE 1 24"	STORM SEWERS, CLASS A, TYPE 2 12"	STORM SEWERS, CLASS A, TYPE 2 15"	STORM SEWERS, CLASS A, TYPE 2 18"	STORM SEWERS, CLASS A, TYPE 2 24"	STORM SEWER (WATER MAIN REQUIREMENTS) 12 INCH	STORM SEWER (WATER MAIN REQUIREMENTS) 15 INCH	STORM SEWER (WATER MAIN REQUIREMENTS) 24 INCH	PIPE UNDERDRAINS 4"	TRENCH BACKFILL
				FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT
60	196+80 RT	196+80 LT	0.55%				73								22.2
61	196+80 LT	198+51 LT	0.57%							54					
62	196+80 RT	197+70 RT												130	
63	196+80 LT	198+60 LT												68	
64	197+70 RT	198+51 LT	0.57%				97							74	9.8
65	197+70 RT	198+19 RT													
66	198+19 RT	198+60 RT	0.57%				53								4.0
67	198+19 RT	198+60 RT												55	
68	198+60 RT	198+60 LT												70	
69	198+51 LT	199+35 LT	0.51%							74					
70	198+60 RT	199+27 RT	0.49%				68								
71	198+51 LT	199+35 LT												87	
72	198+60 RT	199+27 RT												74	
73	199+27 RT	199+35 LT	0.49%				94								19.9
74	199+35 LT	642+63 RT	0.71%										143		53.2
41ST DRIVE CONNECTOR															
75	521+05 LT	521+05 LT	1.67%				12								
76	521+05 LT	521+05 LT	22.40%				20								
77	521+05 RT	521+05 LT	1.15%				41								9.9
78	521+05 RT	521+05 LT												44	
79	522+20 RT	521+05 RT	0.98%				112								21.7
80	522+20 LT	522+20 RT	1.11%				36								4.2
81	527+83 LT	527+83 RT	1.11%				38								7.7
82	527+83 RT	529+43 RT	3.65%								166				33.3
83	529+43 LT	529+43 RT	0.56%				45								12.6
84	529+43 RT	530+03 RT	7.15%				60								22.7
85	531+13 LT	531+03 RT	0.53%				60								24.4
86	531+03 RT	531+86 RT	0.53%				87								30.0
87	531+10 RT	533+03 RT												196	
88	531+13 LT	533+03 LT												175	
89	531+86 RT	531+84 RT	0.18%							22					
90	532+35 RT	531+86 RT	0.15%							46					7.4
91	532+35 LT	532+35 RT	0.33%												7.2
92	533+03 RT	532+35 RT	0.17%			65									2.8
93	533+03 RT	535+10 RT												202	
94	532+83 LT	533+03 LT	0.19%			16									
95	533+03 LT	533+03 RT	0.17%			42									1.3
96	533+03 LT	533+96 LT												80	
97	533+96 RT	533+03 RT	0.46%									91			5.8
98	533+96 LT	533+96 RT	0.21%								42				1.6
99	534+22 LT	533+96 LT	0.32%	19											0.3
100	534+96 LT	535+10 LT	1.00%				7								0.8
101	535+10 LT	535+10 RT	0.53%								49				7.2
102	535+10 LT	537+30 RT												219	
103	535+10 RT	536+00 RT	0.54%				83								12.4
104	535+10 RT	536+90 RT												169	
105	536+00 LT	536+00 RT	0.59%								54				6.3
106	536+00 RT	536+90 RT	0.54%					83							7.0
107	536+90 RT	154+44 LT	0.32%					37							2.2
COALTOWN ROAD															
108	11+10 RT	11+10 LT	0.49%				35								4.0
109	11+10 LT	11+90 LT	0.55%								73				14.1
110	11+90 RT	11+90 LT	0.54%				46								6.0
111	11+10 LT	13+35 LT												218	
112	11+10 RT	13+35 RT												221	
113	11+90 LT	13+35 LT	0.51%									138			47.0
114	13+35 LT	13+35 RT	0.56%					54							40.2
115	13+35 RT	13+45 RT	4.61%					28							
116	13+45 RT	13+55 RT	1.07%					28							
117	14+10 RT	13+35 RT	0.48%				75								3.7
118	15+10 LT	13+35 LT												171	
SUBTOTAL				19	0	123	1184	230	0	196	384	229	143	2253	452.6

FILE NAME: c:\projects\080313108\contract\1\design\misc\sheets\0264884-sh1-Sched2.dgn



Ciorba Group, Inc.
CONSULTING ENGINEERS
6507 North Cumberland Avenue, Suite 402
Chicago, Illinois 60656
Tel. 773.776.4009 Fax 773.776.4014

USER NAME = espino	DESIGNED -	REVISED -
	DRAWN -	REVISED -
PLOT SCALE = 2.0000' / IN.	CHECKED -	REVISED -
PLOT DATE = 3/11/2013	DATE - 3/11/2013	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULE OF QUANTITIES

SCALE:	SHEET NO.	OF	SHEETS	STA.	TO	STA.
--------	-----------	----	--------	------	----	------

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
595	(142-1)R & 142-1)B	ROCK ISLAND	507	58
CONTRACT NO. 64B84				
ILLINOIS FED. AID PROJECT				