

STORM SEWER SCHEDULE (CON'T.)				550A0050	550A0070	550A0120	550A0340	550A0360	550A0380	550A0410	Z0056608	Z0056610	Z0056616	60107600	20800150	
PIPE NO	FROM STR STA	TO STR STA	PIPE SLOPE	STORM SEWERS, CLASS A, TYPE 1 12"	STORM SEWERS, CLASS A, TYPE 1 15"	STORM SEWERS, CLASS A, TYPE 1 24"	STORM SEWERS, CLASS A, TYPE 2 12"	STORM SEWERS, CLASS A, TYPE 2 15"	STORM SEWERS, CLASS A, TYPE 2 18"	STORM SEWERS, CLASS A, TYPE 2 24"	STORM SEWER (WATER MAIN REQUIREMENTS) 12 INCH	STORM SEWER (WATER MAIN REQUIREMENTS) 15 INCH	STORM SEWER (WATER MAIN REQUIREMENTS) 24 INCH	PIPE UNDERDRAINS 4"	TRENCH BACKFILL	
				FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT
119	13+35 RT	14+00 RT													72	
120	14+70 LT	15+10 LT	0.61%								33					4.2
121	16+10 LT	15+10 LT	0.92%								93					9.3
122	15+10 LT	15+16 RT	0.54%					57								8.0
123	15+16 RT	15+19 RT	22.47%					17								
124	15+19 RT	15+25 RT	1.09%					23								
125	16+10 RT	15+16 RT	1.34%				87									
126	15+10 LT	17+90 LT													269	
127	15+16 RT	17+90 RT													265	
128	18+16 RT	18+33 LT													59	
129	18+32 LT	18+93 LT	1.67%								58					7.2
130	18+93 LT	19+85 LT	3.05%								85					
131	17+90 RT	20+75 RT													289	
132	18+95 RT	19+85 RT	3.90%				84									10.0
133	19+85 LT	19+85 RT	0.94%				54									6.1
134	19+85 RT	20+75 RT	3.49%					83								10.1
135	18+93 LT	21+65 LT													277	
136	20+75 RT	21+65 RT	2.61%									82				
137	21+65 LT	21+65 RT	1.46%				61									6.2
138	20+75 RT	21+65 RT													88	
139	21+65 RT	22+70 RT	0.83%					100								8.4
140	21+65 LT	22+63 LT													93	
141	21+65 RT	22+70 RT													103	
142	21+66 LT	21+66 RT													60	
143	22+63 LT	22+70 RT	1.84%				62									4.4
144	22+63 LT	22+70 RT													66	
145	24+95 RT	22+70 RT	1.06%					218								13.5
146	22+63 LT	24+95 LT													227	
147	22+70 RT	24+95 RT													224	
148	22+70 RT	22+86 RT	0.55%						31							
149	24+95 LT	24+95 RT	0.60%				42									4.8
150	24+95 LT	26+95 LT													199	
151	24+95 RT	26+95 RT													200	
152	26+95 RT	24+95 RT	0.71%				194									25.6
153	26+95 LT	26+95 RT	0.60%				42									4.8
38TH STREET NORTH																
154	163+00 LT	163+00 RT	0.54%				46									5.2
155	163+00 RT	162+25 RT	6.32%								68					6.0
156	162+25 RT	162+04 RT	3.46%								41					
SUBTOTAL				0	0	0	672	498	31	0	378	82	0	2491	133.6	
TOTAL				355	57	555	2404	926	382	517	1056	484	200	7923	987	
														TOTAL TRENCH BACKFILL FROM PIPE CULVERT SCHEDULE		460
														TOTAL TRENCH BACKFILL		1447

FILE NAME: m:\proj\080313108\contract\1\design\misc\sheet\026484-ant\Sched25.dgn



**Ciorba Group, Inc.**  
 CONSULTING ENGINEERS  
 5507 North Cumberland Avenue, Suite 402  
 Chicago, Illinois 60656  
 Tel. 773.776.4009 Fax 773.776.4014

USER NAME = espino	DESIGNED -	REVISED -
	DRAWN -	REVISED -
PLOT SCALE = 2.0000' / IN.	CHECKED -	REVISED -
PLOT DATE = 3/11/2013	DATE - 3/11/2013	REVISED -

**STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION**

**SCHEDULE OF QUANTITIES**

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
595	(142-1)R & 142-1HB	ROCK ISLAND	507	59
ILLINOIS FED. AID PROJECT			CONTRACT NO. 64B84	