

60603500			
COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.06			
STATION	STATION	LOCATION	FOOT
PARKING LOT - SE CORNER 38TH & 41ST			
538+41	539+07	RT	88
41ST STREET			
642+59	642+67	RT	8
644+35	644+73	LT	38
645+77	646+22	LT	45
TOTAL			179

60603800			
COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12			
STATION	STATION	LOCATION	FOOT
41ST AVE DRIVE			
540+34	540+64	LT	30
TOTAL			30

60604400			
COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.18			
STATION	STATION	LOCATION	FOOT
41ST DRIVE CONNECTOR			
532+16	533+01	LT	78
533+01	534+12	LT	102
TOTAL			180

60605000			
COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24			
STATION	STATION	LOCATION	FOOT
38TH ST - SOUTH			
150+02	150+72	LT	70
150+72	151+10	LT	82
151+35	151+85	LT	79
151+85	153+68	LT	183
153+68	154+49	LT	116
155+24	155+77	LT	65
155+77	156+80	LT	103
156+80	157+10	LT	32
157+10	157+29	LT	20
150+02	150+75	RT	73
150+75	150+98	RT	50
151+38	151+88	RT	78
151+88	154+05	RT	217
154+05	154+69	RT	115
155+26	156+63	RT	167
156+63	157+43	RT	80
41ST AVE DR			
185+56	189+61	LT	405
189+61	193+15	LT	391
193+15	194+66	LT	151
194+66	196+73	LT	232
196+73	198+78	LT	95
198+78	199+40	LT	65
185+56	189+61	RT	405
189+61	193+15	RT	333
193+15	194+39	RT	124
194+39	196+77	RT	218
196+77	198+36	RT	243
198+36	198+94	RT	58
198+94	199+40	RT	50
41ST DRIVE CONNECTOR			
520+37	520+91	LT	78
520+91	521+33	LT	42
532+25	533+96	LT	171
533+96	534+31	LT	44
534+89	535+13	LT	30
535+13	536+44	LT	131
536+44	537+38	LT	95
538+84	540+21	LT	137
539+63	539+81	LT	28
540+16	540+33	LT	31
520+12	520+39	RT	47
530+16	530+53	RT	102
530+92	531+85	RT	120
531+85	533+46	RT	168
533+46	534+16	RT	73
534+16	537+09	RT	293
534+16		RT	65
534+76		RT	65
539+13	540+66	RT	153
COALTOWN ROAD			
10+00	18+11	LT	811
19+24	24+76	LT	552
24+76	30+00	LT	524
10+00	10+48	RT	48
10+48	11+36	RT	87
11+36	12+23	RT	88
12+23	13+68	RT	145
15+14	16+04	RT	90
16+04	18+17	RT	213
SUBTOTAL			8,731

60605000 (CON'T)			
COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24			
STATION	STATION	LOCATION	FOOT
18+17	19+92	RT	176
19+92	21+37	RT	145
22+80	23+72	RT	92
23+72	30+00	RT	628
23+72	24+11	RT	59
24+30	24+49	RT	52
26+95	27+24	RT	48
27+59	27+89	RT	47
35TH ST			
5+32	5+59	LT	48
5+59	6+50	LT	91
5+10	5+56	RT	66
5+56	6+50	RT	94
38TH ST - NORTH			
161+35	162+48	LT	113
162+48	163+35	LT	88
163+35	163+73	LT	62
161+35	162+08	RT	78
162+08	163+01	RT	93
163+01	163+50	RT	67
SUBTOTAL			2,047
TOTAL			10,778

60900515		
CONCRETE THRUST BLOCK		
LOCATION	STATION	OFFSET
38TH STREET SOUTH		
	154+16	39.64 R
40TH AVENUE		
	134+60	21.04 R
	124+16	26.40 L
41ST AVENUE DRIVE		
	192+47	20.08 R
41ST DRIVE CONNECTOR		
	534+27	41.36 L
*		TBD
TOTAL		6

* LOCATION TBD, SEE SPECIAL PROVISIONS FOR CUT AND CAP EXISTING 8" WATER MAIN.

63000001			
STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS			
STATION	STATION	LOCATION	FOOT
JOHN DEERE ROAD			
266+16	267+91	RT	175
TOTAL			175

63100045		
TRAFFIC BARRIER TERMINAL, TYPE 2		
STATION	LOCATION	EACH
JOHN DEERE ROAD		
268+04	RT	1
TOTAL		1

63100167		
TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT		
STATION	LOCATION	EACH
JOHN DEERE ROAD		
265+66	RT	1
TOTAL		1

63500105				
DELINEATORS				
STATION	OFFSET	LOCATION	PLACEMENT	EACH
265+66		RT	GUARDRAIL	1
122+75		LT	CULVERT	1
122+75		RT	CULVERT	1
821+43		LT	CULVERT	1
136+73		LT	CULVERT	1
136+73		RT	CULVERT	1
TOTAL				6

64300320		
IMPACT ATTENUATORS (FULLY REDIRECTIVE, RESETTABLE), TEST LEVEL 3		
STATION	LOCATION	EACH
JOHN DEERE ROAD		
267+87	CL	1
268+32	CL	1
TOTAL		2

64301090			
ATTENUATOR BASE			
STATION	LENGTH	WIDTH	SQ YD
267+85	32	4.5	16
268+32	32	4.5	16
TOTAL			32

66400305			
CHAIN LINK FENCE, 6'			
STATION	STATION	LOCATION	FOOT
41ST DRIVE CONNECTOR			
524+45.8	524+50.1	RT	69.4
526+53.1	526+57.0	RT	136.8
526+53.1	528+02.0	RT	213.1
524+40.1	524+43.9	LT	68.2
526+59.2	526+65.8	LT	94.6
TOTAL			583

FILE NAME: c:\p\proj\08003193\08\contract\1\design\misc\sheet\0264884-ant-Sched27.dgn



USER NAME = espino	DESIGNED -	REVISED -
PLOT SCALE = 2.0000' / IN.	DRAWN -	REVISED -
PLOT DATE = 3/11/2013	CHECKED -	REVISED -
DATE = 3/11/2013	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE:	SHEET NO.	OF	SHEETS	STA.	TO	STA.
--------	-----------	----	--------	------	----	------

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
595	(142-1)R & 142-1)B	ROCK ISLAND	507	61
CONTRACT NO. 64B84			ILLINOIS FED. AID PROJECT	