

TRAFFIC SIGNAL QUANTITIES

PAY CODE	ITEM	UNIT	38TH ST & 41ST DR CONNECTOR	41ST DR CONNECTOR & 40TH AVE	COALTOWN RD & 41ST DR CONNECTOR	38TH ST & COALTOWN RD	INTERCONNECT	TOTALS
			QUANTITY	QUANTITY	QUANTITY	QUANTITY	QUANTITY	
72000200	SIGN PANEL - TYPE 2	SQ FT	61	47	52	40		200
80500020	SERVICE INSTALLATION - POLE MOUNTED	EACH	1	1	1	1		4
81028740	UNDERGROUND CONDUIT, COILABLE NONMETALLIC CONDUIT, 1 1/2" DIA.	FOOT				7		7
81028750	UNDERGROUND CONDUIT, COILABLE NONMETALLIC CONDUIT, 2" DIA.	FOOT	40	116	75	39	1843	2113
81028760	UNDERGROUND CONDUIT, COILABLE NONMETALLIC CONDUIT, 2 1/2" DIA.	FOOT	62	6		10		78
81028770	UNDERGROUND CONDUIT, COILABLE NONMETALLIC CONDUIT, 3" DIA.	FOOT	35	100	219	169		523
81028790	UNDERGROUND CONDUIT, COILABLE NONMETALLIC CONDUIT, 4" DIA.	FOOT	257	90	216	189		752
81200230	CONDUIT EMBEDDED IN STRUCTURE, 2" DIA., PVC	FOOT		132			1087	1219
81301200	JUNCTION BOX, STAINLESS STEEL, EMBEDDED IN STRUCTURE, 12"X10"X6"	EACH					6	6
81400730	HANDHOLE, COMPOSITE CONCRETE	EACH	3	2	4	5	8	22
81400740	DOUBLE HANDHOLE, COMPOSITE CONCRETE	EACH	2	1	1	1		5
81702110	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 10	FOOT	883	511	896	897		3187
81702130	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 6	FOOT	73	45	102	106		326
87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL, NO. 14 2C	FOOT	1333	186	878	816		3213
87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL, NO. 14 3C	FOOT	1389	200	894	858		3341
87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL, NO. 14 5C	FOOT	863	647	1066	1152		3728
87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL, NO. 14 7C	FOOT	3194	720	1637	1048		6599
87301705	ELECTRIC CABLE IN CONDUIT, COMMUNICATION NO. 18 3 PAIR	FOOT					3541	3541
87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2 C	FOOT	55	55	90	54		254
87301900	ELECTRIC CABLE IN CONDUIT, EQUIPMENT GROUNDING CONDUCTOR, NO. 6 1C	FOOT	570	316	468	565		1919
87502500	TRAFFIC SIGNAL POST, GALVANIZED STEEL 16 FT.	EACH	4	1	1	2		8
87702850	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 24 FT.	EACH		2				2
87702900	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 34 FT.	EACH			1	1		2
87702910	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 36 FT.	EACH				1		1
87702920	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 38 FT.	EACH			1			1
87702940	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 42 FT.	EACH				1		1
87702960	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 46 FT.	EACH		1				1
87702980	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 50 FT.	EACH			1			1



2600 Warrenville Road, Suite 203, Downers Grove, IL 60515
630.705.0110 voice, 630.839.3566 fax
www.mps-il.com

MILLENNIA PROFESSIONAL SERVICES

DESIGNED - TVN
DRAWN - CJD
CHECKED - RPD
DATE - 3/11/2013

REVISED -
REVISED -
REVISED -
REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**TRAFFIC SIGNAL PLAN
SUMMARY OF QUANTITIES**

SCALE: 1=20 SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
595	(142-1)R & 142-1HB	ROCK ISLAND	507	284
CONTRACT NO. 64B84			SQT-1	