

SCHEDULE OF QUANTITIES

70300100 SHORT TERM PAVEMENT MARKING

ROCK ISLAND		LOCATION		COMMENTS	
FOOT RT SIDE	FOOT LT SIDE	TOTAL			
	134	134	944	+	50.00 TO 951 + 20.00 IL 92 / 2 APPL. @ 4' LENGTHS
	134	134	944	+	50.00 TO 951 + 20.00 IL 92 / 2 APPL. @ 4' LENGTHS (CENTER LINES)
	21	21	98	+	62.38 TO 99 + 66.30 140th Street / 2 APPL. @ 4' LENGTHS
0	289	289			

70300220 TEMPORARY PAVEMENT MARKING - LINE 4"

ROCK ISLAND		LOCATION		COMMENTS	
FOOT RT SIDE	FOOT LT SIDE	TOTAL			
500		500	939	+	50.00 TO 944 + 50.00 IL 92 / SOLID YELLOW
	125	125	939	+	50.00 TO 944 + 50.00 IL 92 / SKIP-DASH YELLOW
	670	670	944	+	50.00 TO 951 + 20.00 IL 92 / WHITE EDGE LINE
	845	845	944	+	50.00 TO 946 + 86.00 IL 92 / DOUBLE YELLOW CENTERLINE
	1,022	1,022	948	+	42.00 TO 951 + 20.00 IL 92 / DOUBLE YELLOW CENTERLINE
39		39	948	+	61.00 TO 949 + 00.00 IL 92 / WHITE EDGE LINE
	500	500	951	+	20.00 TO 956 + 20.00 IL 92 / SOLID YELLOW
	125	125	951	+	20.00 TO 956 + 20.00 IL 92 / SKIP-DASH YELLOW
	208	208	98	+	62.38 TO 99 + 66.30 140th Street / DOUBLE YELLOW CENTERLINE
	91	91	98	+	75.00 TO 99 + 64.00 140th Street / WHITE EDGE LINE
	93	93	99	+	36.00 TO 99 + 91.00 140th Street / WHITE EDGE LINE
757	3461	4218			

70300260 TEMPORARY PAVEMENT MARKING - LINE 12"

ROCK ISLAND		LOCATION		COMMENTS	
FOOT RT SIDE	FOOT LT SIDE	TOTAL			
	24	24	944	+	50.00 TO 946 + 86 IL 92 / PAINTED MEDIAN DIAGONALS
	37	37	948	+	42.00 TO 951 + 20 IL 92 / PAINTED MEDIAN DIAGONALS
	61	61			

70300280 TEMPORARY PAVEMENT MARKING - LINE 24"

ROCK ISLAND		LOCATION		COMMENTS	
FOOT RT SIDE	FOOT LT SIDE	TOTAL			
	20	20	99	+	66.30 140TH STREET STOP BAR
	20	20			

70301000 WORK ZONE PAVEMENT MARKING REMOVAL

ROCK ISLAND		LOCATION		COMMENTS	
FOOT RT SIDE	FOOT LT SIDE	SQ FT TOTAL			
	134	44	944	+	50.00 TO 951 + 20.00 IL 92 / 2 APPL. @ 4' LENGTHS
	134	44	944	+	50.00 TO 951 + 20.00 IL 92 / 2 APPL. @ 4' LENGTHS (CENTER LINES)
	21	7	98	+	62.38 TO 99 + 66.30 140th Street / 2 APPL. @ 4' LENGTHS
500		165	939	+	50.00 TO 944 + 50.00 IL 92 / SOLID YELLOW
	125	41	939	+	50.00 TO 944 + 50.00 IL 92 / SKIP-DASH YELLOW
	670	221	944	+	50.00 TO 951 + 20.00 IL 92 / WHITE EDGE LINE
	845	279	944	+	50.00 TO 946 + 86.00 IL 92 / DOUBLE YELLOW CENTERLINE
	1,022	337	948	+	42.00 TO 951 + 20.00 IL 92 / DOUBLE YELLOW CENTERLINE
39		13	948	+	61.00 TO 949 + 00.00 IL 92 / WHITE EDGE LINE
	500	165	951	+	20.00 TO 956 + 20.00 IL 92 / SOLID YELLOW
	125	41	951	+	20.00 TO 956 + 20.00 IL 92 / SKIP-DASH YELLOW
	208	69	98	+	62.38 TO 99 + 66.30 140th Street / DOUBLE YELLOW CENTERLINE
	91	30	98	+	75.00 TO 99 + 64.00 140th Street / WHITE EDGE LINE
	93	31	99	+	36.00 TO 99 + 91.00 140th Street / WHITE EDGE LINE
	24	24	944	+	50.00 TO 946 + 86.00 IL 92 / PAINTED MEDIAN DIAGONALS
	37	37	948	+	42.00 TO 951 + 20.00 IL 92 / PAINTED MEDIAN DIAGONALS
	19	39	99	+	66.30 TO 99 + 66.30 140TH STREET STOP BAR
757	3830	1587			

72400500 RELOCATE SIGN PANEL ASSEMBLY - TYPE A

ROCK ISLAND		LOCATION		OFFSET		COMMENTS	
EACH RT SIDE	EACH LT SIDE	TOTAL					
1		1	732	+	0.00	29.0	RT SB NO PASSING SOUTH OF BRIDGE
	1	1	737	+	50.00		LT NB NO PASSING NORTH OF BRIDGE
	1	1	738	+	22.00	30.0	LT STOP AT CUB SCOUT RD
	1	1	30	+	23.00	31.0	LT STOP AT 99TH AVE
	1	1	947	+	95.00	25.0	LT IL 92 WB 2-DIRECTIONAL ARROW SIGN
1	4	5					

78001110 PAINT PAVEMENT MARKING - LINE 4"

ROCK ISLAND		LOCATION		COMMENTS	
FOOT RT SIDE	FOOT LT SIDE	TOTAL			
					WHITE
		825	729	+	20.00 TO 733 + 32.50 SOUTH EAST WHITE EDGE LINE, 2 APPL.
		825	729	+	20.00 TO 733 + 32.50 SOUTH WEST WHITE EDGE LINE, 2 APPL.
		294	733	+	32.50 TO 734 + 79.50 BRIDGE EAST WHITE EDGE LINE, 2 APPL.
		294	733	+	32.50 TO 734 + 79.50 BRIDGE WEST WHITE EDGE LINE, 2 APPL.
		1,041	734	+	79.50 TO 740 + 0.00 NORTH EAST WHITE EDGE LINE, 2 APPL.
		1,041	734	+	79.50 TO 740 + 0.00 NORTH WEST WHITE EDGE LINE, 2 APPL.
		1,340	946	+	50.00 TO 950 + 0.00 IL 92 / WHITE EDGE LINE / 2 APPL.
		78	948	+	61.19 TO 949 + 0.00 IL 92 / WHITE EDGE LINE / 2 APPL.
		182	98	+	75.00 TO 99 + 63.33 140TH ST / WHITE EDGE LINE / 2 APPL.
		185	99	+	36.19 TO 99 + 90.44 140TH ST / WHITE EDGE LINE / 2 APPL.
2423	3682	6105			
					YELLOW
		32	729	+	20.00 TO 729 + 36.00 SOUTH YELLOW NPZ SOLID, 2 APPL.
		206	729	+	20.00 TO 733 + 32.50 SOUTH YELLOW CENTER DASH, 2 APPL.
		74	733	+	32.50 TO 734 + 79.50 BRIDGE YELLOW CENTER DASH, 2 APPL.
		260	734	+	79.50 TO 740 + 0.00 NORTH YELLOW CENTER DASH, 2 APPL.
		500	737	+	50.00 TO 740 + 0.00 NORTH YELLOW NPZ SOLID, 2 APPL.
		335	944	+	50.00 TO 951 + 20.00 IL 92 / YELLOW CENTER DASH / 2 APPL.
		53	98	+	62.38 TO 99 + 66.30 140TH ST / YELLOW CENTER DASH / 2 APPL.
1460	0	1460			
		7565			

78001180 PAINT PAVEMENT MARKING - LINE 24"

ROCK ISLAND		LOCATION		OFFSET		COMMENTS	
FOOT RT SIDE	FOOT LT SIDE	TOTAL					
							WHITE
		36	738	+	25.50 TO 738 + 43.5 29.5	LT	CUB SCOUT RD STOP - WHITE, 2 APPL.
		36	30	+	24.00		99TH AVE STOP - WHITE, 2 APPL.
		40	99	+	66.30		140TH STREET STOP BAR / 2 APPL.
76	36	112					

78100100 RAISED REFLECTIVE PAVEMENT MARKER

ROCK ISLAND		LOCATION		COMMENTS	
EACH		TOTAL			
6		6	729	+	20.00 TO 733 + 32.50 SOUTH OF BRIDGE
7		7	734	+	79.50 TO 740 + 0.00 NORTH OF BRIDGE
13	0	13			

78200410 GUARDRAIL MARKERS, TYPE A

ROCK ISLAND		LOCATION		COMMENTS	
EACH RT SIDE	EACH LT SIDE	TOTAL			
4		4	731	+	85.35 TO 733 + 53.50 S. OF BRIDGE, EAST SHLDR; 4 MIN. / SECT.
	4	4	730	+	47.85 TO 733 + 53.50 S. OF BRIDGE, WEST SHLDR; 4 MIN. / SECT.
4		4	734	+	58.50 TO 736 + 1.64 N. OF BRIDGE, EAST SHLDR; 4 MIN. / SECT.
	4	4	734	+	58.50 TO 736 + 26.65 N. OF BRIDGE, WEST SHLDR; 4 MIN. / SECT.
8	8	16			

78200520 BARRIER WALL MARKERS, TYPE B

ROCK ISLAND		LOCATION		COMMENTS	
EACH RT SIDE	EACH LT SIDE	TOTAL			
2		2	733	+	53.50 TO 734 + 58.50 EAST PARAPET, 2 MIN. PER WALL
	2	2	733	+	53.50 TO 734 + 58.50 WEST PARAPET, 2 MIN. PER WALL
2	2	4			

78201000 TERMINAL MARKER - DIRECT APPLIED

ROCK ISLAND		LOCATION		COMMENTS	
EACH RT SIDE	EACH LT SIDE	TOTAL			
1		1	730	+	47.85 17.0 LT SOUTH OF BRIDGE, WEST SHOULDER
	1	1	731	+	85.35 17.0 RT SOUTH OF BRIDGE, EAST SHOULDER
1		1	736	+	1.64 17.0 RT NORTH OF BRIDGE, EAST SHOULDER
	1	1	736	+	26.65 17.0 LT NORTH OF BRIDGE, WEST SHOULDER
2	2	4			

78300100 PAVEMENT MARKING REMOVAL

ROCK ISLAND		LOCATION		COMMENTS	
SQ FT RT SIDE	SQ FT LT SIDE	TOTAL			
	56	56	944	+	50.00 TO 951 + 20.00 IL 92 / YELLOW CENTER DASH
	223	223	944	+	50.00 TO 951 + 20.00 IL 92 / WHITE EDGE LINE
	9	9	98	+	62.38 TO 99 + 66.30 140TH ST / YELLOW CENTER DASH
0	9	288			

Z0004552 APPROACH SLAB REMOVAL

ROCK ISLAND		LOCATION		COMMENTS	
SQ YD		TOTAL			
67		67	733	+	60.50 TO 733 + 90.50 SOUTH EXISTING APPROACH
67		67	734	+	21.30 TO 734 + 51.30 NORTH EXISTING APPROACH
134		134			

Z0020900 ESTABLISHING AND REFERENCING LAND SECTION MARKERS

ROCK ISLAND		LOCATION		OFFSET		COMMENTS	
EACH RT SIDE	EACH LT SIDE	TOTAL					
1		1	739	+	35.88	3.5	RT QUARTER SECTION CORNER NEAR 99TH AVE
1	0	1					

Z0028415 GEOTECHNICAL REINFORCEMENT

ROCK ISLAND		LOCATION		COMMENTS	
SQ YD RT SIDE	SQ YD LT SIDE	TOTAL			
		353	729	+	20.00 TO 733 + 38.50 WEST SHOULDER, SOUTH OF BRIDGE
		375	729	+	20.00 TO 733 + 38.50 EAST SHOULDER, SOUTH OF BRIDGE
		321	734	+	73.50 TO 740 + 0.00 WEST SHOULDER, NORTH OF BRIDGE
		361	734	+	73.50 TO 738 + 66.50 EAST SHOULDER, NORTH OF BRIDGE
736	674	1410			

X0327301 RELOCATE EXISTING MAILBOX

ROCK ISLAND		LOCATION		COMMENTS	
EACH		TOTAL			
1		1	947	+	20.00 IL 92 WESTBOUND
3		3	948	+	95.00 IL 92 WESTBOUND
4		4			

X4401198 HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH

ROCK ISLAND		LOCATION		COMMENTS	
SQ YD		TOTAL			
75		75	738	+	70.00 TO 739 + 0.00 TRANSITION FROM 2.25" TO 1.5" SURF. REM.
75	0	75			

X5960110 GRANULAR BACKFILL FOR STRUCTURES

ROCK ISLAND		LOCATION		COMMENTS	
CU YD		TOTAL			
12		12	733	+	32.50 TO 733 + 46.50 UNDER S. APPROACH FOOTING
13		13	734	+	65.50 TO 734 + 79.50 UNDER N. APPROACH FOOTING
220		220			AT BRIDGE ABUTMENTS
245		245			

DATE	BY	SURVEYED	PLOTTED	CHECKED	FILED
PLAN	NO.	NOTE BOOK	NO.	DATE	

DATE	BY	PROFILE	GRADES	NOTED	CHKD
NOTE BOOK	NO.	STRUCTURE	NO.	DATE	

FILE NAME = D:\200807-ent\sch_03.dgn



USER NAME = mszmur-lo	DESIGNED KAC	REVISED
DRAWN KMB	REVISED	
PLOT SCALE = 2.0000' / in.	CHECKED KAC	REVISED
PLOT DATE = 6/19/2013	DATE 05-03-2013	REVISED

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

</