

PLAN	SURVEYED	DATE
NOTE BOOK NO.	PLOTTED	BY
	ALIGNMENT	
	CHECKED	
	FILE NAME	

PROFILE	SURVEYED	DATE
NOTE BOOK NO.	GRADES CHECKED	BY
	STRUCTURE	
	NOTATRS CHKD	

EARTHWORK SCHEDULE

LOCATION	20200100	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE (25%) (CU YD)	EMBANKMENT (CU YD)	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) (CU YD)	20400800	20300100
	EARTH EXCAVATION (CU YD)				FURNISHED EXCAVATION (CU YD)	CHANNEL EXCAVATION (CU YD)
IL 92						
STA. 729+17.0 TO STA. 733+68.0	390	293	1418	-1126	1126	
STA. 734+45.0 TO STA. 740+00.0	1132	849	2809	-1960	1960	
STA. 944+50.0 TO STA. 951+20.0	309	232	9	222	-222	
99TH AVE						
STA. 30+42.0 TO STA. 31+50.0	465	349	0	349	-349	
140TH ST						
STA. 98+75.0 TO STA. 99+63.3	62	47	0	47	-47	
BIG BRANCH CREEK						
STA. 10+00 TO STA. 11+22			18	-18	18	2390
TOTAL IL 92	2358	1769	4254	-2486	2490	2390

SHRINKAGE FACTORS
EARTH EXCAVATION 25%

HOT-MIX ASPHALT SCHEDULE

LOCATION	30300011	30300112	35102000	35102400	40600625	40603310	40701851	40800050	42001430	48203023
	AGGREGATE SUBGRADE IMPROVEMENT (TON)	AGGREGATE SUBGRADE IMPROVEMENT, 12" (SQ YD)	AGGREGATE BASE COURSE, TYPE B 8" (SQ YD)	AGGREGATE BASE COURSE, TYPE B 12" (SQ YD)	LEVELING BINDER (MACHINE METHOD), N50 (TON)	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50 (TON)	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 8 1/2" (SQ YD)	INCIDENTAL ASPHALT SURFACING (TON)	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE) (SQ YD)	HOT-MIX ASPHALT SHOULDERS, 6 1/2" (SQ YD)
IL 92 MAINLINE										
STA. 729+20.0 TO STA. 733+38.5 (24' WIDTH)	256				1322	92			25	
STA. 734+73.5 TO STA. 740+00.0 (24' WIDTH)	188				1570	116			25	
EAST SHOULDER										
STA. 729+20.0 TO STA. 732+16.4 (8' WIDTH)*		280				22				262
STA. 732+16.4 TO STA. 733+32.5 (7' WIDTH)		95				8				90
STA. 734+79.5 TO STA. 735+76.6 (7' WIDTH)		81				6				76
STA. 735+76.6 TO STA. 738+66.5 (8' WIDTH)*		276				22				263
WEST SHOULDER										
STA. 729+20.0 TO STA. 730+78.9 (8' WIDTH)*		149				11				132
STA. 730+78.9 TO STA. 733+32.5 (7' WIDTH)		209				17				197
STA. 734+79.5 TO STA. 736+60.7 (7' WIDTH)*		152				12				142
STA. 736+60.7 TO STA. 740+00.0 (4' WIDTH)		192				13				149
99TH AVE										
STA. 738+66.5 TO STA. 739+88.6 (3" SURFACE) (VAR. WIDTH)				360				66		
IL 92 INTERSECTION IMPROVEMENTS										
STA. 944+50.0 TO STA. 951+20.0 (VAR. WIDTH)		648	193				648	25		
140TH ST										
STA. 98+75.0 TO STA. 99+63.3 (NB) (VAR. WIDTH)		77					77			
STA. 99+36.3 TO STA. 99+91.0 (SB) (VAR. WIDTH)		69					69			
CUB SCOUT RD										
STA. 738+08.0 TO STA. 738+72.0 (2" SURFACE) (VAR. WIDTH)			140					18		
TOTAL IL 92	444	2228	333	360	2892	319	794	109	50	1311

* INCLUDES SHOULDER WIDENING FOR TRAFFIC BARRIER TERMINAL

FILE NAME = D206907.shl.sch_B4.dgn



USER NAME = mszmurlo	DESIGNED KAC	REVISED
	DRAWN KMB	REVISED
PLOT SCALE = 2.0000' / in.	CHECKED KAC	REVISED
PLOT DATE = 6/19/2013	DATE 05-03-2013	REVISED

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

IL 92 OVER BIG BRANCH CREEK
SCHEDULE OF QUANTITIES

SCALE: SHEET NO. 4 OF 4 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
599	103MFT-BR	ROCK ISLAND	88	19
CONTRACT NO. 64D18				
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		