

SUMMARY OF QUANTITIES

CONST. CODE	CONST. CODE	CONST. CODE
100% STATE	80% FEDERAL 20% STATE	80% FEDERAL 20% STATE
ROADWAY	ROADWAY	BRIDGE
0004	0004	0011

CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	CONST. CODE		STRUCTURE NO. 081-0196
				RURAL	RURAL	
28100107	STONE RIPRAP, CLASS A4	SQ YD	375		375	
28100109	STONE RIPRAP, CLASS A5	SQ YD	1,120			1,120
28200200	FILTER FABRIC	SQ YD	1,495		375	1,120
30300011	AGGREGATE SUBGRADE IMPROVEMENT	TON	444		444	
30300112	AGGREGATE SUBGRADE IMPROVEMENT 12"	SQ YD	2,228		2,228	
35102000	AGGREGATE BASE COURSE, TYPE B 8"	SQ YD	333		333	
35102400	AGGREGATE BASE COURSE, TYPE B 12"	SQ YD	360		360	
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	2,892		2,892	
40600895	CONSTRUCTING TEST STRIP	EACH	1		1	
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	319		319	
40701851	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 8 1/2"	SQ YD	794		794	
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	109		109	
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	50		50	
44000100	PAVEMENT REMOVAL	SQ YD	129		129	

Δ INDICATES SPECIALTY ITEM.

PLAN
DATE
BY
REVISIONS
PLOTTED
CHECKED
DATE
BY
NOTE BOOK NO.
STRUCTURE NO.
FILE NAME

PROFILE
DATE
BY
REVISIONS
PLOTTED
CHECKED
DATE
BY
NOTE BOOK NO.
STRUCTURE NO.
FILE NAME

FILE NAME = 0205897_sht.ecc.02.dgn



USER NAME = mzmurlo	DESIGNED KAC	REVISED
	DRAWN KMB	REVISED
PLOT SCALE = 2.0000' / 1" = 1'	CHECKED KAC	REVISED
PLOT DATE = 6/19/2013	DATE 05-03-2013	REVISED

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**IL 92 OVER BIG BRANCH CREEK
SUMMARY OF QUANTITIES**

SCALE: SHEET NO. 2 OF 7 SHEETS STA. TO STA.

F.A.P. RTE. 599	SECTION 103MFT-BR	COUNTY ROCK ISLAND	TOTAL SHEETS 88	SHEET NO. 5
CONTRACT NO. 64018			FED. ROAD DIST. NO. [ILLINOIS] FED. AID PROJECT	