

SUMMARY OF QUANTITIES

PLAN
DATE
BY
SUBMITTED
PLOTTED
CHECKED
DATE
FILE NAME

PROFILE
DATE
BY
SUBMITTED
PLOTTED
CHECKED
DATE
FILE NAME

CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	CONST. CODE		
				100% STATE ROADWAY 0004	80% FEDERAL 20% STATE ROADWAY 0004	80% FEDERAL 20% STATE BRIDGE 0011
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	249		249	
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	370		370	
44000400	GUTTER REMOVAL	FOOT	360		360	
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	954		954	
44004000	PAVED DITCH REMOVAL	FOOT	168		168	
44004250	PAVED SHOULDER REMOVAL	SQ YD	1,331		1,331	
48203023	HOT-MIX ASPHALT SHOULDERS, 6 1/2"	SQ YD	1,311		1,311	
50100300	REMOVAL OF EXISTING STRUCTURES NO. 1	EACH	1			1
50105220	PIPE CULVERT REMOVAL	FOOT	41		41	
50200100	STRUCTURE EXCAVATION	CU YD	184			184
50300225	CONCRETE STRUCTURES	CU YD	102.2			102.2
50300255	CONCRETE SUPERSTRUCTURE	CU YD	199.3			199.3
50300260	BRIDGE DECK GROOVING	SQ YD	464			464
50300300	PROTECTIVE COAT	SQ YD	576			576
50401005	FURNISHING AND ERECTING PRECAST PRESTRESSED CONCRETE I-BEAMS, 48 IN.	FOOT	446			446

Δ INDICATES SPECIALTY ITEM.



USER NAME * mzmurlo	DESIGNED KAC	REVISED
PLOT SCALE * 2.0000' / 1"	DRAWN KMB	REVISED
PLOT DATE * 6/19/2013	CHECKED KAC	REVISED
	DATE 05-03-2013	REVISED

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**IL 92 OVER BIG BRANCH CREEK
SUMMARY OF QUANTITIES**

SCALE: SHEET NO. 3 OF 7 SHEETS STA. TO STA.

F.A.P. RTE. 599	SECTION 103MFT-BR	COUNTY ROCK ISLAND	TOTAL SHEETS 88	SHEET NO. 6
CONTRACT NO. 64D18			ILLINOIS FED. AID PROJECT	

FILE NAME * D:\5997_911_903.dwg