

**SUMMARY OF QUANTITIES**

PLAN  
 SUBMITTED BY \_\_\_\_\_ DATE \_\_\_\_\_  
 REVISIONS BY \_\_\_\_\_ DATE \_\_\_\_\_  
 CHECKED BY \_\_\_\_\_ DATE \_\_\_\_\_  
 NOTE BOOK NO. \_\_\_\_\_  
 DATE FILED \_\_\_\_\_

PROFILE  
 SUBMITTED BY \_\_\_\_\_ DATE \_\_\_\_\_  
 PLOTTED BY \_\_\_\_\_ DATE \_\_\_\_\_  
 CHECKED BY \_\_\_\_\_ DATE \_\_\_\_\_  
 NOTE BOOK NO. \_\_\_\_\_  
 DATE FILED \_\_\_\_\_

CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	CONST. CODE		
				100% STATE ROADWAY 0004	80% FEDERAL 20% STATE ROADWAY 0004	80% FEDERAL 20% STATE BRIDGE 0011
				RURAL	RURAL	RURAL
				STRUCTURE NO. 081-0196		
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	60,540			60,540
51201800	FURNISHING STEEL PILES HP14X73	FOOT	220			220
51202305	DRIVING PILES	FOOT	220			220
51203800	TEST PILE STEEL HP14X73	EACH	2			2
51204650	PILE SHOES	EACH	12			12
51500100	NAME PLATES	EACH	1			1
542D0220	PIPE CULVERTS, CLASS D, TYPE 1 15"	FOOT	56		56	
542D5485	PIPE CULVERTS, CLASS D, TYPE 1 EQUIVALENT ROUND-SIZE 30"	FOOT	60		60	
54213445	END SECTIONS 10"	EACH	1		1	
54213870	STEEL END SECTIONS 15"	EACH	2		2	
54215145	STEEL END SECTIONS, EQUIVALENT ROUND-SIZE 30"	EACH	2		2	
55100700	STORM SEWER REMOVAL 15"	FOOT	47		47	
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	108			108
60100080	FRENCH DRAINS	CU YD	8		8	
60100935	PIPE DRAINS 10"	FOOT	14		14	

Δ INDICATES SPECIALTY ITEM.

FILE NAME = 0225207.dwg



USER NAME: mazurlo	DESIGNED: KAC	REVISED:
PLOT SCALE: 2.0000' / 1"	DRAWN: KMB	REVISED:
PLOT DATE: 6/19/2013	CHECKED: KAC	REVISED:
	DATE: 05-03-2013	REVISED:

**STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION**

**IL 92 OVER BIG BRANCH CREEK  
 SUMMARY OF QUANTITIES**

SCALE: SHEET NO. 4 OF 7 SHEETS STA. TO STA.

F.A.P. RTE. 599	SECTION 103MFT-BR	COUNTY ROCK ISLAND	TOTAL SHEETS 88	SHEET NO. 7
FED. ROAD DIST. NO. ILLINOIS		FED. AID PROJECT CONTRACT NO. 64D18		