



# Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

September 6, 2013

SUBJECT: FAS Route 200 (IL 172)  
Project ACRS-0200(107)  
Section 141B-2  
Whiteside County  
Contract No. 64D81  
Item No. 28, 9/20/13 Letting  
Addendum A

## NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised page 6 of the Special Provisions.

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

John D. Baranzelli, P.E.  
Acting Engineer of Design and Environment

A handwritten signature in cursive script, reading "Ted B. Walschleger P.E.".

By: Ted B. Walschleger, P. E.  
Engineer of Project Management

cc: Paul Loete, Region 2, District 2; Tim Kell; D. Carl Puzey; Estimates

## **COMPLETION DATE PLUS WORKING DAYS**

Effective: December 29, 2006

Revised: April 12, 2011

Revised Article 108.05(b) of the Standard Specifications to read:

“(b) Completion Date Plus Working Days. When a completion date plus working days is specified, the Contractor shall complete the project by 11:59 p.m. on or prior to August 15, 2014. The PROJECT shall have all work completed, except the landscape items, punch list items, and MOWING for the PROJECT to be considered complete.

The Contractor will be allowed 15 working days after the completion date to complete landscaping items, punch list items and MOWING.

## **START DATE**

No work shall be started on this project until March 17, 2014 without written approval from the Resident Engineer, except for the following:

- Pavement widening and associated work at the northwest corner of IL Route 40 and Hahnaman Road.

## **GUARDRAIL REMOVAL**

Effective: August 20, 1990

Revised: August 26, 1997

This work shall be done according to Section 632 of the Standard Specifications except that all removed guardrail will become the property of the Contractor.

This work will be paid for at the contract unit price per Foot for GUARDRAIL REMOVAL, measured from center-to-center of end post.

## **MOWING**

This work consists of mowing all Seeding Class 1 and Class 2A at the completion of the project or before winter shut down. The vegetation must be at least 6” long before mowing. The vegetation shall be mowed to obtain a height of not more than 3 inches. All debris must be cleared from the right-of-way immediately after the mowing.

This work will be paid for at the contract unit price per Acre for MOWING.

Revised 9/6/13