


SUMMARY OF QUANTITIES

CONSTRUCTION CODE TYPE:				FUNDING: 80% FED : 20% STATE	
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	0004 ROADWAY	0011 SN 098-0044 (EX) SN 098-0119 (PR)
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	4696	4696	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	14	14	
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	6	6	
* 78200520	BARRIER WALL MARKERS, TYPE B	EACH	2	2	
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	6	6	
X2070304	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	156		156
X2810110	STONE RIPRAP, CLASS A5 (SPECIAL)	SO YD	744		744
X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1	
Z0001900	ASBESTOS BEARING PAD REMOVAL	EACH	26		26
Z0004552	APPROACH SLAB REMOVAL	SO YD	106	106	
Z0004638	PAVEMENT BREAKING	SO YD	905	905	
Z0046304	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	128		128
Z0049300	REFERENCING LAND SECTION MARKERS	EACH	1	1	

* SPECIALTY ITEMS

FILE NAME : #FILE#	USER NAME : #USER#	DESIGNED - RAC	REVISED -	<p align="center">STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</p>	 <p>Zraka Engineering, P.C. 4216 North Heritage Chicago, IL 60613</p>	<p align="center">SUMMARY OF QUANTITIES</p>	F.A.S. RTE. 200	SECTION 141B-2	COUNTY WHITESIDE	TOTAL SHEETS 77	SHEET NO. 9
PLOT SCALE : #SCALE#	CHECKED - DAZ	REVISED -	SCALE:				SHEET 5 OF 5 SHEETS	STA. 283+43 TO STA. 293+50	CONTRACT NO. 64081		
PLOT DATE : #DATE#	DATE - 06-21-13	REVISED -	ILLINOIS FED. AID PROJECT								