


SUMMARY OF QUANTITIES					FUNDING: 80% FED : 20% STATE			
CONSTRUCTION CODE TYPE:			TOTAL	0004	0011	0011	0040	
CODE NO.	ITEM	UNIT	QUANTITY	ROADWAY	SN 008-0029 (EX) SN 008-0049 (PR)	SN 008-0030 (EX) SN 008-0050 (PR)	SN 008-1106 (PR)	
* 25100630	EROSION CONTROL BLANKET	SO YD	4132	4132				
* 25100900	TURF REINFORCEMENT MAT	SO YD	368	368				
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	351	351				
28000305	TEMPORARY DITCH CHECKS	FOOT	250	250				
28000400	PERIMETER EROSION BARRIER	FOOT	1840	1840				
28000500	INLET AND PIPE PROTECTION	EACH	8	8				
28100105	STONE RIPRAP, CLASS A3	SO YD	133	133				
28100109	STONE RIPRAP, CLASS A5	SO YD	2812		1364	1400	48	
28200200	FILTER FABRIC	SO YD	2945	133	1364	1400	48	
30300011	AGGREGATE SUBGRADE IMPROVEMENT	TON	726	726				
30300112	AGGREGATE SUBGRADE IMPROVEMENT 12"	SO YD	3419	3419				
35102000	AGGREGATE BASE COURSE, TYPE B 8"	SO YD	882	882				
35102400	AGGREGATE BASE COURSE, TYPE B 12"	SO YD	352	352				
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	8119	8119				

SPECIALTY ITEMS

FILE NAME : #FILE#	USER NAME : #USER#	DESIGNED - RAC	REVISIONS -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	 Zroka Engineering, P.C. 4216 North Hermitage Chicago, IL 60613	SUMMARY OF QUANTITIES	F.A.P. RTE. 17	SECTION 4BR-5 & 4BR-6	COUNTY CARROLL	TOTAL SHEETS 150	SHEET NO. 6		
	PLOT SCALE : #SCALE#	DRAWN - LCR	REVISIONS -				SCALE:	SHEET 2 OF 9 SHEETS	STA. TO STA.	ILLINOIS FED. AID PROJECT			
	PLOT DATE : #DATE#	CHECKED - DAZ	REVISIONS -										
		DATE - 06-28-13	REVISIONS -										