


SUMMARY OF QUANTITIES				FUNDING: 80% FED : 20% STATE			
CONSTRUCTION CODE TYPE:			TOTAL	0004	0011	0011	0040
CODE NO.	ITEM	UNIT	QUANTITY	ROADWAY	SN 008-0029 (EX) SN 008-0049 (PR)	SN 008-0030 (EX) SN 008-0050 (PR)	SN 008-1106 (PR)
50201123	COFFERDAM (TYPE 2) (LOCATION - 3)	EACH	1			1	
50201124	COFFERDAM (TYPE 2) (LOCATION - 4)	EACH	1			1	
50300225	CONCRETE STRUCTURES	CU YD	374.6		159.7	184.5	30.4
50300255	CONCRETE SUPERSTRUCTURE	CU YD	647.7		330.8	316.9	
50300260	BRIDGE DECK GROOVING	SQ YD	1516		780	736	
50300265	SEAL COAT CONCRETE	CU YD	210.4		98.9	111.5	
50300280	CONCRETE ENCASEMENT	CU YD	8.0		4.0	4.0	
50300300	PROTECTIVE COAT	SQ YD	1884		963	921	
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1		0.5	0.5	
50500505	STUD SHEAR CONNECTORS	EACH	9216		4878	4338	
50800105	REINFORCEMENT BARS	POUND	6020				6020
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	193380		96880	96500	
50800515	BAR SPLICERS	EACH	1778		910	868	
51201400	FURNISHING STEEL PILES HP10X42	FOOT	395			395	

SPECIALTY ITEMS

FILE NAME :	USER NAME : #USER#	DESIGNED - RAC	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	 Zroka Engineering, P.C. 4216 North Homewood Chicago, IL 60613	SUMMARY OF QUANTITIES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
#FILE#	DRAWN - LCR	REVISED -	17				4BR-5 & 4BR-6	CARROLL	150	8	
PLOT SCALE : #SCALE#	CHECKED - DAZ	REVISED -	CONTRACT NO. 64083								
PLOT DATE : #DATE#	DATE - 06-28-13	REVISED -	SCALE:	SHEET 4 OF 9 SHEETS	STA. TO STA.	ILLINOIS FED. AID PROJECT					